

**HLL Lifecare Ltd, KANAGALA**

**ANNEXURE**

**Name of the work- Replacement of Top Arch sheets at Auditorium.**

<b>Sl. No</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1	Removing of MS frame work work glass and disposing/stacking the material including all fabrication work etc complete as directed by Engineer-in-charge. Size of the frame-Appx-40mX1.0M	L/s	1		
2	Removing of old damaged GI sheets with MS angles, truss and stacking/disposing the material as directed by Engineer-in-charge.	Sqm	65		
3	Providing, fabricating & fixing using MS square/ rectangular sections 5/6mm thick, 100X100X6/5, 100X50X5/6, 80x80x6/5, 60X60X6/5, 50X50X6/5, 40X40X5/6 MS plate with anchor bolts for roofing structure. making necessary holes in the masonry/ concrete & proper laying of the box finishing with concrete/plaster including two coats of oil paint with zinc primer etc complete as directed by EIC.	Kg	1250		
4	Providing & fixing pre coated profile GI sheets & ridges of 0.50 mm thick of approved make all these sheets to be fixed to purling using self tapping screws or J-hooks, EPDM seal, metal washer, including labor, fixing new sheets with cutting the wall/beam & finishing with civil work, painting touch up etc complete. (Make-TATA/Jindal)	Sqm	160		
	<b>Total amount</b>				

The work should be carried out at Appx-10mtr height.

Contractor sign with seal