

Amendment No: 2

to

Tender no. HLL/ID/JIPMER/UHC –02/15/36 Dtd:08.01.2016

for

CONSTRUCTION OF URBAN HEALTH CENTER AT KURISIKUPPAM FOR JIPMER

at

**JAWAHARLAL INSTITUTE OF POSTGRADUATE MEDICAL EDUCATION & RESEARCH ,
PUDUCHERRY****Ref:** Tender no. HLL/ID/JIPMER/UHC –02/15/36 Dtd:08.01.2016

The following amendments are incorporated in the referred tender document:

PART III ,Special Conditions of Contract & Price Bid, Part B Page 27					
For:					
S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
5	Supplying and filling in plinth with Jamuna sand under floors including watering, Ramming, Consolidating and dressing complete	142	cum		
Read As:					
S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
5	Supplying and filling in plinth with sand under floors including watering, Ramming, Consolidating and dressing complete	142	cum		

PART III ,Special Conditions of Contract & Price Bid, Part B Page 31**For:**

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
28	Marble work gang saw cut (polished and machine cut) of thickness 18 mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1cement : 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement :2 marble dust) with an admixture of pigment to match the marble shade (To be secured to the backing by means of cramps, which shall be paid for separately).				
29	Providing and fixing cramps of required size & shape in RCC/ CC / Brick masonry backing with cement mortar 1:2 (1 cement :2 coarse sand), including drilling necessary hole in stones and embedding the cramp in the hole (fastener to be paid separately).				
	Stainless steel cramps	3.40	kg		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
28	Marble work gang saw cut (polished and machine cut) of thickness 18 mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1cement : 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement :2 marble dust) with an admixture of pigment to match the marble shade (To be secured to the backing by means of clamps, which shall be paid for separately).				
29	Providing and fixing cramps of required size & shape in RCC/ CC / Brick masonry backing with cement mortar 1:2 (1 cement :2 coarse sand), including drilling necessary hole in stones and embedding the clamp in the hole (fastener to be paid separately).				
	Stainless steel clamps	3.40	kg		

PART III ,Special Conditions of Contract & Price Bid, Part B Page 32

For:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
32	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :	23.5	Sqm		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
32	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to				

	40 mm thick :				
	Second Class Teak wood	15.50	Sq m		
	Float Glass 5.5mm thick glass panes	8	sqm		

PART III ,Special Conditions of Contract & Price Bid, Part B Page 33

For:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
38	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	100mm	272	Each		
	75mm	246	Each		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
38	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	150mm	272	Each		
	100mm	246	Each		

PART III ,Special Conditions of Contract & Price Bid, Part B Page 38**For:**

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
64	Supplying and filling in plinth with Jamuna sand under floors including watering, Ramming, Consolidating and dressing complete./Moorum/sand zone V (Jamuna)	20	cum		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
64	Supplying and filling in plinth with sand under floors including watering, Ramming, Consolidating and dressing complete./Moorum/sand	20	cum		

PART III ,Special Conditions of Contract & Price Bid, Part c Page 49**For:**

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
3	Supplying and filling in plinth with Jamuna sand under floors including watering, Ramming, Consolidating and dressing complete	8.88	cum		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
3	Supplying and filling in plinth with sand	8.88	cum		

	under floors including watering, Ramming, Consolidating and dressing complete.				
--	--	--	--	--	--

PART III ,Special Conditions of Contract & Price Bid, Part D Page 60

For:					
S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
60	Supply of 2x28W, indoor surface mountable fluorescent CRCA sheet steel power coated body light fixture, 28W T5 lamp, electronic HPF ballast, lamp holder, prewired complete with all necessary accessories suitable for operation on 230V, 50Hz AC supply as required (Wipro WIF 20228 SG or equivalent)	84	Each		
61	Supply of 1x28W, indoor surface mountable fluorescent CRCA sheet steel power coated body light fixture, 28W T5 lamp, electronic HPF ballast, lamp holder, prewired complete with all necessary accessories suitable for operation on 230V, 50Hz AC supply as required (Wipro WIF 20128 SG or equivalent)	14	Each		
62	Supply of 1200 mm sweep min three star rated ceiling fan complete with motor, double ball bearing, blades, canopy, 30 cm down rod and without speed regulator suitable for 230 V 50 HZ, AC supply confirms to IS 374/1979 as required	59	Each		

	complete. (Make Usha Technix or equivalent).				
63	Supply of 300mm sweep, metal blades with safety guard suitable for single phase 230 volt, 50Hz AC supply complete with motor, capacitor and all accessories as required complete. (Make : Usha Turbo or equivalent)	8	Each		
Read As:					
S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
60	Supply of 2x28W, indoor surface mountable fluorescent CRCA sheet steel power coated body light fixture, 28W T5 lamp, electronic HPF ballast, lamp holder, prewired complete with all necessary accessories suitable for operation on 230V, 50Hz AC supply as required. Make: Refer list of approved make	84	Each		
61	Supply of 1x28W, indoor surface mountable fluorescent CRCA sheet steel power coated body light fixture, 28W T5 lamp, electronic HPF ballast, lamp holder, prewired complete with all necessary accessories suitable for operation on 230V, 50Hz AC supply as required. Make: Refer list of approved make	14	Each		
62	Supply of 1200 mm sweep min three star rated ceiling fan complete with motor, double ball bearing, blades, canopy, 30 cm down rod and without	59	Each		

	speed regulator suitable for 230 V 50 HZ, AC supply confirms to IS 374/1979 as required complete. Make: Refer list of approved make				
63	Supply of 300mm sweep, metal blades with safety guard suitable for single phase 230 volt, 50Hz AC supply complete with motor, capacitor and all accessories as required complete. Make: Refer list of approved make	8	Each		

PART III ,Special Conditions of Contract & Price Bid, Part D Page 65

For:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
73	Supply, installation, testing & commissioning of IP66,150W MH street lighting, with die cast aluminium housing, anodised aluminum reflector, toughened glass, stainless steel toggle, heavy duty copper ballast, pf capacitor, 1x150W MH lamp etc as required. The light fitting shall be suitably installed with all required accessories to poles. The item shall include 3C x 1.5 sqmm PVC insulated copper unarmoured cable for connecting between the luminaire and the loop in loop out box. (Similar to Wipro WSH 71150 or equivalent).	5	Nos		
79	Supply, Installation & Testing of GE/Morley/Honeywell make addressable	20	Nos		

	Photoelectric type Smoke detector for below false ceiling with base plate.				
80	Supply, Installation & Testing of GE / Morley/honeywell make addressable photoelectric type Heat detector with base plate	20	Nos		
Read As:					
S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
73	Supply, installation, testing & commissioning of IP66,150W MH street lighting, with die cast aluminium housing, anodised aluminum reflector, toughened glass, stainless steel toggle, heavy duty copper ballast, pf capacitor, 1x150W MH lamp etc as required. The light fitting shall be suitably installed with all required accessories to poles. The item shall include 3C x 1.5 sqmm PVC insulated copper unarmoured cable for connecting between the luminaire and the loop in loop out box. Make: Refer list of approved make	5	Nos		
79	Supply, Installation & Testing of addressable Photoelectric type Smoke detector for below false ceiling with base plate. Make: Refer list of approved make	20	Nos		
80	Supply, Installation & Testing of addressable photoelectric type Heat detector with base plate. Make: Refer list of approved make	20	Nos		

PART III ,Special Conditions of Contract & Price Bid, Part D Page 66**For:**

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
87	Supply, Installation, Testing & commissioning of Two Loop non - expandable addressable type Fire Alarm Panel with Battery backup with capacity for 99 addressable devices including event logging facility, printing facility, interface feature & including all necessary hardware & accessories, etc. complete as required. (GE / Morley)	1	Nos		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
87	Supply, Installation, Testing & commissioning of Two Loop non - expandable addressable type Fire Alarm Panel with Battery backup with capacity for 99 addressable devices including event logging facility, printing facility, interface feature & including all necessary hardware & accessories, etc. complete as required. Make: Refer list of approved make	1	Nos		

PART III ,Special Conditions of Contract & Price Bid, Part D Page 66 & 67**For:**

S. No	Description	Quantity	Unit	Rate in	Amount in
-------	-------------	----------	------	---------	-----------

				Figures and words (Rs.)	Figures and words(Rs.)
89	<p>Supply, installation, testing & commissioning of electric traction type elevator of following capacity and type suitable for operation on 415 V, 3 phase, 50 Hz AC supply, having AC variable voltage and variable frequency type traction control, with machine room, speed of 1.00 Mtr/sec, electromagnetic brake system, simple operations, operating control panel with luminous buttons, overload warning indicator, battery operated alarm bell, LED type emergency light, intercom suitable for hook up to EPABX, infrared ray sensing door protection for full height, reverse phase relay on controller, fireman's switch at ground floor, digital car positions indicator in car and at all positions indicator in car and at all floors with Up/DOWN direction, all signal fixtures in stainless steel faceplates, light fixtures, ventilation fan, etc complete with all accessories including automatic rescue device in the event of power failure etc., as required.</p>				
	<p>The traction motor placed directly above the hoistway in Machine Room and elevator shall be of geared type with travel height of 12.mtrs. (suitable for lift well size 3000mm (D)X</p>				

	2350m(W)) complete as per technical specification, simplex full collective operation with/without attendant. Car/Hoistway Entrance, protected by stainless steel hairline doors and clear side(telescopic) opening min 1200mm x 2000mm height. Complete with necessary scaffolding, electrical panel, logic control panel and shaft lighting etc required for the erection of the elevators				
	8 passengers (Minimum) capacity (minimum 940 Kgs) elevator, 3 stops & 3 openings car size of 1300mm wide x2400mm deep x 2300mm Height Inside dimensions and entrance at front side on all the serving floors, provided with matt finish stainless steel panel on all four side, stainless steel mirror finish ceiling, stainless steel hand rail on three sides complete as per specifications.	1	Each		

Read As:

S. No	Description	Quantity	Unit	Rate in Figures and words (Rs.)	Amount in Figures and words(Rs.)
89	Supply, installation, testing & commissioning of electric traction type elevator of following capacity and type suitable for operation on 415 V, 3 phase, 50 Hz AC supply, having AC variable voltage and variable frequency type traction control, with machine room, speed of				

	<p>1.00 Mtr/sec, electromagnetic brake system, simple operations, operating control panel with luminous buttons, overload warning indicator, battery operated alarm bell, LED type emergency light, intercom suitable for hook up to EPABX, infrared ray sensing door protection for full height, reverse phase relay on controller, fireman's switch at ground floor, digital car positions indicator in car and at all positions indicator in car and at all floors with Up/DOWN direction, all signal fixtures in stainless steel faceplates, light fixtures, ventilation fan, etc complete with all accessories including automatic rescue device in the event of power failure etc., as required.</p>				
	<p>The traction motor placed directly above the hoistway in Machine Room and elevator shall be of geared type with travel height of 12.mtrs. (suitable for lift well size 3000mm (D)X 2350m(W)) complete as per technical specification, simplex full collective operation with/without attendant. Car/Hoistway Entrance, protected by stainless steel hairline doors and clear side(telescopic) opening min 1200mm x 2000mm height. Complete with necessary scaffolding, electrical panel, logic control panel and shaft</p>				

	lighting etc required for the erection of the elevators				
	15 passengers bed lift elevator, 3 stops & 3 openings car size of 1300mm wide x2400mm deep x 2300mm Height Inside dimensions and entrance at front side on all the serving floors, provided with matt finish stainless steel panel on all four side, stainless steel mirror finish ceiling, stainless steel hand rail on three sides complete as per specifications.	1	Each		

All other terms and conditions remain unaltered.

.....End.....