

HLL LIFECARE LIMITED, KANAGALA

ANNEXURE

Name of the work-Providing Shed,compound wall & concrete flooring with levelling for newly installed DG set no-05.

Sl.No	Description	Unit	Qty	Rate	Amount
1	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clouds including shifting the debris outside complete as per specifications.	Cum	9		
2	Earth work excavation for Foundation & levelling removing the excavated earth to a distance not exceeding 50 M with a lift up to 1.50 m including refilling of excavated earth wherever required.	Cum	26		
3	Filling in plinth with murum from excavated stuff or selected earth brought from outside by spreading, watering and well consolidating in layers not exceeding 150mm thickness at a time etc. complete as directed.				
	a)Filling by excavated earth (only labour charges)	Cum	2		
	(b) Filling by out side earth (material &labour charges)	Cum	35		
4	Providing & laying M 7.5 (1:4:8) Granite or Basalt or trap jelly concrete using 40 mm & down size jelly for foundation laid in 15 cms thick layers & well compacted including curing etc complete..	Cum	9		
5	Providing & laying granite or basalt or trap jelly cement concrete (1:3:6) using 20 mm& down size jelly including mixing, laying, tamping, curing & smooth finishing for exposed faces & with necessary centering & form work etc., complete. Sills & coping & any other such works.	Cum	27		
6	Providing & constructing brick masonry with approved quality of modular brick of standard size with necessary scaffolding, curing for basement & super structure in C.M 1:6	Cum	11.5		
7	Providing (12mm) plastering to internal surfaces including curing, scaffolding, rounding of all corners wherever required smooth rendering in CM 1:4 with 12 mm thick plaster.	Sqm	280		

8	Providing, fabricating & fixing M.S angle 5/6mm thick, ISLC 125X70X5/6, 100X50X6/5, 75x40x6/5, 65X65X6/5, 50X50X6/5, MS plate with anchor bolts for roofing structure. Including painting of two coats of oil paint over a coat of zinc primer of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the angle finishing with concrete/plaster etc complete as directed by EIC.	Kg	1970		
9	Providing & fixing pre coated profile GI sheets & ridges of 0.50 mm thick of approved make all these sheets to be fixed to purling using self tapping screws or J-hooks, EPDM seal, metal washer, including labor, fixing new sheets etc complete. (Make-TATA/Jindal)	Sqm	145		
Total amount					

Contractor Sign with seal