

MINISTRY OF HEALTH & FAMILY WELFARE

GOVERNMENT OF INDIA, NEW DELHI

Tender No. MoHFW /AIIMS-RISHIKESH/BBW-MW/HLL/ID/2014

Request for Proposal (RFP)  
*for*

**SETTING UP OF RESIDENTIAL COMPLEX  
AT AIIMS RISHIKESH  
(SH: Balance Building Works- Miscellaneous Works)**

The Complete Tender Documents consist of the following:

- Volume- I (NIB & ITB)
- Volume-II (GCC & SCC)
- Volume-III ( Tech. Specs)
- Volume-IV (BOQ)

**Volume – IV(Revised)**

- **Bill of Quantities**



B-14A, Sector – 62,  
NOIDA (UP) -201307

Phone no: 0120-4071500, Fax no: 0120-4071513

(March, 2014)



**PROJECT: SETTING UP OF RESIDENTIAL COMPLEX AT AIIMS RISHIKESH  
(SH: BALANCE BUILDING WORKS-RESIDENTIAL QUARTERS )  
FINANCIAL BID SUMMARY SHEET**

SR. NO	SUB-HEAD	Quoted Amount in Figures (Rs.)	Quoted Amount in Words (Rs.)
1	Miscellaneous Works		
	<b>TOTAL AMOUNT</b>		



PROJECT: SETTING UP OF RESIDENTIAL COMPLEX AT AIIMS RISHIKESH (SH: BALANCE BUILDING WORKS- MISCELLANEOUS WORKS)			
FINANCIAL BID SUMMARY SHEET MISCELLANEOUS WORKS			
SR. NO	SUB-HEAD	Quoted Amount in Figures (Rs.)	Quoted Amount in Words (Rs.)
1	EXPANSION JOINT		
2	WOOD AND PVC AND ALUMINIUM WORK		
3	FLOORING		
4	RAIN WATER PIPE		
5	FINISHING		
	<b>TOTAL AMOUNT</b>		



**PROJECT: SETTING UP OF RESIDENTIAL COMPLEX AT AIIMS RISHIKESH  
(SH: BALANCE BUILDING WORKS-MISCELLANEOUS WORKS)**

**MISCELLANEOUS CIVIL WORKS BOQ**

Sl. No.	DSR Item No	Description of Work	QTY	Unit	Rates in Rs (in)	Rates in Rs (in Words)	Amount in Rs (in Figures)	Amount in Rs (in Words))
10		<b>Expansion joint</b>						
11	NSR	Expansion joint 100 mm width X 450 mm deep :-Providing and fixing in position 12mm/18 mm,/25 mm thick and 450 mm width bitumen impregnated factory made fibre board in combination with each other (Make -JOLLY BOARD or equivalent )conforming to IS: 1838,as required to fill/fit in expansion joint of average with 100 mm and 450 mm depth,including cost of cleaning etc. of Expansion joint. Work should be carried as per the direction of Engineer-in-charge.						
a		12 mm thick	1102.00	sqm				
b		18 mm thick	1102.00	sqm				
c		25 mm thick	2647.00	sqm				
12								
	NSR	Providing and fixing ACP sheet of 150mm wide covering over expansion joints with powder coated screws as per design. Eye hole for screw on side of ACP is required complete in all respects as per the direction of Engineer-in-charge						
13	NSR	Providing and laying 25X12mm Polysulphide expansion joints sealent of approved make applied with masking tape and grinding etc complete in all respects as per direction of the Engineer-In-charge	1800.00	m				
			208.00	m				



<b>NSR</b>	Cutting & making of 25mm wide or as required at site floor joints in flooring of tile/kota etc with joint cutting machine including making the vertical surfaces good & disposal of rubbish etc complete as directed by Engineer-in-charge.	203.00	m				
	<b>Expansion Joint Sub Head Total :-</b>						
	<b>Wood and PVC Work And Aluminium Work</b>						
<b>9.102</b>	Providing and fixing aluminum casement stays ISI marked anodized (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour and shade with necessary screws etc. complete.	5500.00	each				
<b>9.21</b>	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part-I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters :						
<b>9.21.1</b>	35mm thick including ISI marked stainless steel butt hinges with necessary screws.	20.00	sqm				
<b>9.62</b>	Providing and fixing ISI marked oxidized M.S. sliding door bolts with nuts and screws etc. complete.						
<b>9.62.2</b>	250 x 16 mm	50.00	each				
<b>9.63</b>	Providing and fixing ISI marked oxidized M.S. tower bolts black finish, (Barrel Type) with necessary screws etc. complete.						
<b>9.63.1</b>	250 x 10 mm	50.00	each				
<b>9.63.3</b>	150 x 10 mm	50.00	each				
<b>9.66</b>	Providing and fixing ISI marked oxidized MS handles conforming to IS : 4992 with necessary screws etc. complete.						
<b>9.66.1</b>	125 mm	50.00	each				



7	9.82	Providing and fixing bright finished brass hanging type floor door stopper with necessary screws, etc. complete.	50.00	each				
8	9.47	Providing and fixing nickel plated M.S. pipe curtain rods with nickel plated bracket:						
	9.47.2	25 mm dia (heavy type)	2500.00	metre				
9	9.97	Providing and fixing Aluminium Tower Bolts, ISI Marked, anodised ( Anodic Coating not less than AC 10 as per IS 1868), transparent or dyed to required colour or shade with necessary screws etc. complete:						
	9.97.4	150x10 mm	50.00	each				
		<b>Wood And PVC Work And Aluminium Work:-</b>						
0		<b>Flooring</b>						
1	NSR	Making of Moulding in treads of steps of Kota stone slab						
2	8.6	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.	3500.00	metre				
		<b>Flooring Sub Head Total:-</b>	3000.00	sqm				
0		<b>Rain water Pipe</b>						
1	NSR	Providing and fixing 50 mm diameter and 60 cm long rain water spout using pvc pipes in cement mortar 1:4(1 cement :4 fine sand).						
2	NSR	Extra for making / cutting hole over kota skirting of required diameter for fixing 50 mm diameter rain water spout and their finishing.	50.00	each				
3	12.46	Providing and fixing to the inlet mouth of rain water pipe PTMT (an Engineering Thermoplastic) grating square (Slit) 150 mm square with a height of 8 mm and weighing not less than 100 gms.	50.00	each				
		<b>Rain Water Pipe Sub Head Total:-</b>	400.00	each				



0	<b>Finishing</b>							
1	13.26	Providing and applying plaster of paris putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete.	100.00	sqm				
2	13.37	White washing with lime to give an even shade						
	13.37.1	New work ( three or more coats )	100.00	sqm				
3	13.41	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade						
	13.41.1	new work (two or more coats) over and including priming coat with cement primer.	10000.00	sqm				
4	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :						
	13.61.1	Two or more coats on new work	500.00	sqm				
5	13.47	Finishing wall with Premium Acrylic smooth exterior paint with silicone additives of required shade						
	13.47.1	New work (two or more coats applied @1.43 ltr /10sqm) over and including base coat of water proofing cement paint applied @2.20 kg / 10 sqm	71405.00	sqm				
		<b>Finishing Sub Head Total:-</b>						
		<b>Total</b>						

