

Amendment no.2

10th Sept ,2015

Sub : Supply & Installation of Automatic Online Chemical Dosing System as per tender specifications at HLL, IFC, Irapuram, Kochi.

Ref : IFB No:HLL/CED/IFC/ ACD /2015 Dated 22-08-2015

With reference to the above, we here by incorporate the following amendment to the tender documents as detailed below :

Amendment no.1

The last date of date for receipt and opening of bid of the above referred tender has been amended as follows.

- (a) Last date and time of receipt of tender : 16-09-2015,15.00Hrs
- (b) Date and time of opening tender : 16-09-2015, 15.30Hrs
- (c) Schedule V,Format for quoting

EXISTING

SCHEDULE V
FORMAT FOR QUOTING

Sub: Providing Automatic Online Chemical Dosing System for HLL CDM at IFC					
SI No	Item/Work Description	Unit	Quantity	Rate in Rs	Amount in Rs
1	Supply & Installation of SS pipes (SS316) with necessary fittings as per drawing and specifications for the following sizes				
a)	25mm seamless SS 316 pipe	MTRS	10.00		
b)	25mm SS Flange (threaded)	Nos.	2.00		
c)	25mm SS Ball Valve(Make : Minerva/Audco/GG)	Nos.	2.00		
d)	25 mm SS nipple	Nos.	2.00		
e)	40mm motorised drain valve	Nos.	2.00		
2	Fabrication & fixing of structural platform using the following SS materials				
a)	50/38 mm SS square tube(Material will be supplied by HLL)	MTRS	50.00		
b)	Supply & Installation of 4mm thick MS chequered plate including painting with one coat synchromite primer & two coat enamel paint of approved quality.	KG	130.00		
3	Supply & Installation of SS Tank as per drawing				
a)	SS Tank having size-1000mmX1000mmX1000mmx2mm(L x W x H x T)	Nos.	1.00		
4	Supply,Fabrication & fixing of MS Angle (40x40x4mm)supports including painting with one coat synchromite primer & two coat enamel paint of approved quality.	Kg	25.00		
5	Supply & Installation of GI U-clamps with nut,bolt,washer etc. complete for pipe line				
a)	For 75mm PVC pipes	Nos.	10.00		
b)	For 50 mm SS pipes	Nos.	10.00		
c)	For 25mm SS pipes	Nos.	10.00		
6	Supply & installation of Chemical dosing pump for TSP(Tri Sodium Phosphate) , Ammonia application Geared Motor Spec: Rating : 0.25 Kw , 3-ph . Direct Drive Geared motor , Motor speed : 1500 RPM , Output : 2 kg/m ² Make:Bolfiglioli/Sumitomo, Power Input : 3 Phase AC , 50 Hz 440 V Enclosure : IP 66 Dut class : S1 Temperature class : F Cooling : Fan cooled Factor of Safety : >1.5 Surface and corrosive protection : OKS- S(corrosive category : C3), Efficiency class : IE 1. Specification of Pump Type:Chemical pump, Discharge :40m3/hr Head : 10mtr MOC : SS316 Application : Trisodium Phosphate Speed :1500RPM Suction : 1 1/2" Delivery : 1"	Nos.	2.00		

7	Supply and Installation of Solenoid Valve with accessories				
a)	Solenoid valve (5/2) with 6" PU tube(50 Mtrs) with suitable connectors, Tee connectors.As per relevant IS/IEC Standards with test and calibration certificates	Set	4.00		
8	Supply and Installation of Level sensors				
a)	Ultrasonic level sensors for TSP(Tri sodium phosphate),Ammonia applicationAs per IS/IEC 60947-5-2 , level should be indicated digitally.	Nos.	1.00		
9	Supply and Installation of PLC				
a)	PLC for dosing application(10 bit PLC 5/5 I/O)As per IS/IEC 61131-3/IEC 61499/IEC 61508	Set	1.00		
10	Supply and Installation of Panel board Panel wiring should be as per IS 732 & Earthing of Panel should be as per IS 3043/IEC 60364 , Panel should be as per IS 8437(Part 1&2) / IEC 60479-1&2 , IS 60529/IEC 60529 , IS 9409/IEC 61140 ,IS 9676, IS 5216 with Test Certificates)				
a)	Panel Board with size 600x600x210 mm with 2 mm Powder Coated CRCA Sheet.	Set	1.00		
11	Supply and Installaion of MCCBAs per IS 13032 , IS 13947/IEC 60947-5-2 , IS 9409/IEC 61140 , IS 8623 (part 1 to 3)/IEC 60439(1to 3), IS 8504/IEC 60216-4-2 , IS 60715/IEC 60715 ,IS 60898/IEC 60898 , IS 60947(Part 1&2)/IEC 60947, IS 10118(Part 1 to 4) , IS 60529/IEC 60529 , IS 9676 with test certificates.				
a)	63 A , 3 Pole 450 V MCB	Nos.	1.00		
12	Supply and Installation of MCB(As per IS 13032 , IS 13947/IEC 60947-5-2 , IS 9409/IEC 61140 , IS 8623 (part 1 to 3)/IEC 60439(1to 3), IS 8504/IEC 60216-4-2 , IS 60715/IEC 60715 ,IS 60898/IEC 60898 , IS 60947(Part 1&2)/IEC 60947, IS 10118(Part 1 to 4) , IS 60529/IEC 60529 , IS 9676 with test certificates				
a)	10 A , 3 Pole ,415 V MCB	Nos.	2.00		
13	6A , 2pole , 230 V MCB	Nos.	2.00		
14	Supply and Installation of online-starters As per IS 60947(Part 4 & Section 2)/ IEC 60947-4-1 & 2 Standards with Test Certificate				
a)	0-4 A , 3 Pole 415 V (1HP)	Nos.	1.00		
15	Supply and Installation of TimerAs per relevant IS/IEC Standards with test and calibration certificates				
a)	Digital Timer(programmable type, 0-20minutes)	Nos.	2.00		
16	Supply and Installation of Power Supply(24 V DC) sourceAs per IEC 61850-3/IEC 60950-1with Test & Calibration Certificates				
a)	Power Supply(24 V DC) source	Nos.	1.00		
17	Supply of motorised flow valves with size 2" As per relevant IS/IEC standards	Nos.	4.00		
BASIC PRICE					
SERVICE TAXES & OTHER TAXES IF ANY					
GROSS AMOUNT IN RS. (INCLUDING TAXES)					
(IN WORDS)					
I agree to execute the works as per schedule, at the rates quoted by me as above					
SIGNATURE OF THE CONTRACTOR					

READ AS

SCHEDULE V
FORMAT FOR QUOTING

Sub: Providing Automatic Online Chemical Dosing System for HLL CDM at IFC					
SI No	Item/Work Description	Unit	Quantity	Rate in Rs	Amount in Rs
1	Supply & Installation of SS pipes (SS316) with necessary fittings as per drawing and specifications for the following sizes				
a)	25mm seamless SS 316 pipe	MTRS	10.00		
b)	25mm SS Flange (threaded)	Nos.	2.00		
c)	25mm SS Ball Valve(Make : Minerva/Audco/GG)	Nos.	2.00		
d)	25 mm SS nipple	Nos.	2.00		
e)	40mm motorised drain valve	Nos.	2.00		
2	Fabrication & fixing of structural platform using the following SS materials				
a)	50/38 mm SS square tube(Material will be supplied by HLL)	MTRS	50.00		
b)	Supply & Installation of 4mm thick MS chequered plate including painting with one coat synchromite primer & two coat enamel paint of approved quality.	KG	130.00		
3	Supply & Installation of SS Tank as per drawing				
a)	SS Tank having size-1000mmX1000mmX1000mmx2mm(L x W x H x T)	Nos.	1.00		
4	Supply,Fabrication & fixing of MS Angle (40x40x4mm)supports including painting with one coat synchromite primer & two coat enamel paint of approved quality.				
		Kg	25.00		
5	Supply & Installation of GI U-clamps with nut,bolt,washer etc. complete for pipe line				
a)	For 75mm PVC pipes	Nos.	10.00		
b)	For 50 mm SS pipes	Nos.	10.00		
c)	For 25mm SS pipes	Nos.	10.00		
6	Supply& Installation of Chemical Pump as per specification <u>Specification of Pump</u> Capacity : 40m ³ /hr. Type : Chemical Application : Trisodium Phosphate MOC: SS316 Speed : 1500RPM Suction :1 1/2" Delivery : 1" Make : Grundfos <u>Specification of Motor</u> Power : 0.75KW,1HP,3PH	Nos.	2.00		

	Speed : 1500RPM Make : ABB/Siemens/Grundfos				
7	Supply and Installation of Solenoid Valve with accessories				
a)	Solenoid valve (5/2) with 6" PU tube(50 Mtrs) with suitable connectors, Tee connectors.As per relevant IS/IEC Standards with test and calibration certificates	Set	4.00		
8	Supply and Installation of Level sensors				
a)	Ultrasonic level sensors for TSP(Tri sodium phosphate),Ammonia applicationAs per IS/IEC 60947-5-2 , level should be indicated digitaly.	Nos.	1.00		
9	Supply and Installation of PLC				
a)	PLC for dosing application(10 bit PLC 5/5 I/O)As per IS/IEC 61131-3/IEC 61499/IEC 61508	Set	1.00		
10	Supply and Installation of Panel board Panel wiring should be as per IS 732 & Earthing of Panel should be as per IS 3043/IEC 60364 , Panel should be as per IS 8437(Part 1&2) / IEC 60479-1&2 , IS 60529/IEC 60529 , IS 9409/IEC 61140 ,IS 9676, IS 5216 with Test Certificates)				
a)	Panel Board with size 600x600x210 mm with 2 mm Powder Coated CRCA Sheet.	Set	1.00		
11	Supply and Installaion of MCCBAs per IS 13032 , IS 13947/IEC 60947-5-2 , IS 9409/IEC 61140 , IS 8623 (part 1 to 3)/IEC 60439(1to 3), IS 8504/IEC 60216-4-2 , IS 60715/IEC 60715 ,IS 60898/IEC 60898 , IS 60947(Part 1&2)/IEC 60947, IS 10118(Part 1 to 4) , IS 60529/IEC 60529 , IS 9676 with test certificates.				
a)	63 A , 3 Pole 450 V MCB	Nos.	1.00		
12	Supply and Installation of MCB(As per IS 13032 , IS 13947/IEC 60947-5-2 , IS 9409/IEC 61140 , IS 8623 (part 1 to 3)/IEC 60439(1to 3), IS 8504/IEC 60216-4-2 , IS 60715/IEC 60715 ,IS 60898/IEC 60898 , IS 60947(Part 1&2)/IEC 60947, IS 10118(Part 1 to 4) , IS 60529/IEC 60529 , IS 9676 with test certificates				
a)	10 A ,3 Pole ,415 V MCB	Nos.	2.00		
13	6A , 2pole , 230 V MCB	Nos.	2.00		
14	Supply and Installation of online-starters As per IS 60947(Part 4 & Section 2)/ IEC 60947-4-1 & 2 Standards with Test Certificate				
a)	0-4 A , 3 Pole 415 V (1HP)	Nos.	1.00		
15	Supply and Installation of TimerAs per relevant IS/IEC Standards with test and cslibration certificates				
a)	Digital Timer(programmable type, 0-20minutes)	Nos.	2.00		
16	Supply and Installation of Power Supply(24 V DC) sourceAs per IEC 61850-3/IEC 60950-1with Test & Calibration Certificates				
a)	Power Supply(24 V DC) source	Nos.	1.00		
17	Supply of motorised flow valves with size 2"As per relevant IS/IEC standards	Nos.	4.00		
BASIC PRICE					
SERVICE TAXES & OTHER TAXES IF ANY					
GROSS AMOUNT IN RS. (INCLUDING TAXES)					
(IN WORDS)					
I agree to execute the works as per schedule, at the rates quoted by me as above					
SIGNATURE OF THE CONTRACTOR					

All other conditions are as per original IFB No:HLL/CED/IFC/ ACD /2015 Dated 22-08-2015

ASSOCIATE VICE PRESIDENT