

Modification of Corridor between Primary and Secondary Plant at Kanagala Factory of HLL, Belgaum

Prebid meeting on 21.11.2014

SI. No	Description	Query by Contractors	Reply by HLL
1	Sl. No.: 04 (Glazing of Wall Tiles)	Height of the wall tiling	Wall tile for skirting and height is 150 mm
2	Sl. No.: 15,16 & 17 (Aluminium work)	Kindly provide the list of aluminium work	View Panel at moulding area
3	Sl. No.: 19 (ACP work)	Drawing for ACP works	The bidder before start of the ACP work, the shop drawing shall be submitted and got approved from HLL
4	Sl. No.: 20 (Floor Tiling)	Method of tile laying	Floor tile may be laid over the existing tile by using of reputed make adhesive instead of cement mortar
5	Sl. No.: 21 (False ceiling)	Epoxy powder coating may be recommended for operation theatre and clean room and also is very costly.	Normal powder coat is sufficient for corridor work instead of epoxy powder coating
6	Sl. No.: 24 (Steel Door)	Kindly give the approved make of steel door	Shakti met-Dor Ltd/Dortek/GMPtech/Ahalada