

SCHEDULE OF QUANTITIES					
AMRIT Pharmacy at Guwahati Medical College and Hospital					
Size : 31 Ft X 18 Ft = 558 SqFt					
Sl. NO.	ITEM	UNIT	QUANTITY	Basic Rate(in Rs.)	AMOUNT (in Rs.)
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, 12mm Thk Ply with Laminate in the bottom and 8mm Thk Float glass in Top all complete as per architectural drawings and the directions of Engineer-in-charge	SqM	19.25		
2	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters	SqM	19.25		
3	Providing and fixing ball bearing for rolling shutters.	Each	2.00		
4	Extra for providing mechanical device chain and crank operation for operating rolling shutters.	Each	1.00		
5	Internal paint : 1 Coat primer, 2 coats water base paint distemper.	SqM	95.60		
6	Providing and fixing with 1.5sqmm and 2.5sqmm FRLS Copper wire, 20/25mm PVC conduit, Concealed M.S. Switch box, Modular Plates, Switches, fan Regulator, Sockets, Switches, For Light points, fan, AC, fridge, Camera Power, Computer Power, Sign board, with material and Labour.	Point	28.00		
7	Providing and fixing MDB with 1 No 2 Pole ELCB, 4 Nos Single pole MCB, Dressing, Termination and Commissioning.	Set	1.00		

8	Lan/ Networking wiring only with data socket, plate, box, labour all complete as per drawing.	Mtr	15.00		
9	providing and crimping socket for Lan wire connect to computer	Nos.	4.00		
10	Providing and fixing pre wired LED light fittings 600mm X 600mm as per detail with labour testing and commissing etc as required.	Nos.	8.00		
11	providing and fixing ceiling fan 1200mm white in colour with clamp, labour all complete.	Nos.	2.00		
12	Supply, laying and testing of under noted sizes of Aluminium conductor XLPE insulated PVC sheathed & sleeved armoured and overall PVC sleeved 1.1 KV grade power distribution cables conforming to relevant IS code and as per specification in ground (in existing trenches) through pipe or on wall / racks cable trays including dressing and clamping the cable with MS zinc passivated clamps etc. as required.				
a	4 x 16 sq.mm	Mtr	30.00		
13	Supplying & making of end terminations with brass compression gland and Al. lugs for following sizes of PVC insulated and PVC sheathed/ XLPE Al. conductor cable of 1.1 KV grade as required.				
a	4 x 16 sq.mm	Set	2.00		
14	Supply,installation,testing and commissioning of Digital camera, 0.5 lux with 3/ 4 mm fixed lens with IR Leds for Day and night vision or equivalent complete as required in mini dome shape fixed type, including all wiring from the control module in existing PVC conduits complete as required. Make: honeywell, bosch, Hikvision, samsung	Set	5.00		
15	Supply,installation,testing and commissioning of 8 – channel colour HD Video Mgmt system with 8 cameras inputs Built in multiplexer, Digital Video recorder, Video motion Detection system, aalong with 15" monitor, TCPIP network feature for remote monitoring & 500GB HDD Make: honeywell, bosch, Hikvision, samsung or equilant.	Each	1.00		
16	Supply, installation , testing & commissioning 2trn split aircondition , including indoor and outdoor units , copper piping, drain piping, insulation, control and power cables between outdoor and indoor units, complete as required by Engineer-in Charge. Make: Voltas, Bluestar, Daikin. With 3.0 Mtr Standard Copper Pipe and Drain	Set	2.00		

17	<p>GRID CEILING : 600mm X 600mm SQUARE ASBESTOS CEILING WITH 24mm GRID.</p> <p>INSTALLATION: To comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using same make suspension system at 1200mm maximum centre & not more than 150mm from spliced joints. The First/Last suspension system at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. All Perimeter trim to be of wall angles, secured to walls at 450 mm maximum centres.</p>	Sft	558.00		
18	<p>MEDIUM SIZE MEDICAL STORAGE RACKS TYPE A:</p> <p>Open Wooden display laminated cabinets in plywood at the free floor area with proper provision of racks and shelves.</p> <p>Maximum height of the cabinet is depending upon the available height at the location. 600mm deep prelaminated storage unit with 18mm commercial ply shelves laminated bothside with front edge polish/painted and shutters fixed with hinges to be provided. The height of 600mm deep storage shall be 750mm from the ground. Rest of the height - 450mm wide 10mm thk clear float glass shelves to be fixed between laminated vertical 18 mm ply with back. shelves to be fix with proper bracket holders. as per layout drawing.</p> <p>Note: Storage unite to include: Shutters of 18mm thick prelamine, 10mm thick, back ply, hinges, individual locks, 150mm long 10mm dia 'H' handle, edge polish/painted match with outer laminate colour.</p> <p>Make laminate :Greenlam - 283 Sky blue / Merino / Century.</p>	Sq. ft	300.00		

19	<p>MEDIUM SIZE MEDICAL STORAGE RACKS TYPE B: Open Wooden display laminated cabinets in plywood at the free floor area with proper provision of racks and shelves. Maximum height of the cabinet is depending upon the available height at the location. 450 mm deep prelaminated storage unit with 18mm commercial ply shelves laminated bothside with front edge polish/painted and shutters fixed with hinges to be provided. The height of 450mm deep storage shall be 750mm from the ground . Rest of the height - 400mm wide 10mm thk clear float glass shelves to be fixed between laminated vertical 12 mm ply with 10mm back Ply. shelves to be fix with proper bracket holders.</p> <p>Note: Storage unite to include: Shutters of 18mm thick prelamine, 10mm thick back ply, hinges, individual locks, 10mm dia 'H' handle, edge polish/painted match with outer laminate colour. Make laminate :Greenlam - 283 Sky blue / Merino / Century.</p>	Sft	216.92		
20	<p>COUNTER FOR MEDICAL: single level Counter of 900 mm from ground and Counter top at 1050 mm level. 18mm thk granite/marble to be used for counter top on 18mm thick commercial ply. Under counter storage unit (below 900 mm) to be fixed with individual locks and handles as per app. 600mm wide laminated door and openable counter top to be part of the counter as per design. The counter ends at both sides shall be in such a way that, it effectively separates the customers from the storage area. Cash drawer of suitable design is to be installed.</p> <p>Make PLYWOOD: Commercial. LAMINATE: GREENLAM, MARINO OR EQUIVALANT.</p>	Sq. ft	65.10		
21	Working Table, 3'0" X 2'0" with 18mm Ply top and two Vertical support in store room as per DRW, with colour laminated sheet finish.	Nos	1.00		
22	Revolving height adjustable chair with arm rest.	Nos.	5.00		
23	SIGN BOARD: Box Type Sign board with back Light and coloured transperant flex on front as per given design and letter. fittings will be with out stand.	Sft	31.75		
24	Supplying and fixing of carbon dioxide fire extinguisher type 2 kgs. Capacity of approved make with wall mounting bracket as required conforming to IS: 2878/1976 (Push type).	Nos	1.00		

	Total Amount for Work		
	Applicable Taxes & Statutory payments(Pl.specify)		
	GRAND TOTAL (Final Bid Amount)		