

HLL LIFECARE LTD,KANGALA.

ANNEXURE

NAME OF WORK: Development of ETP area.

SI. No	Description	Unit	Qty.	Rate	Amount
1	Earth work excavation in Hard soil for foundation & removing the excavated earth to a distance not exceeding 50m with a lift upto 1.50m & shifting debris outside.	cum	20.00		
2	Providing and laying Granite and trap jelly concrete of 20cm using 40mm & down size jelly for foundation laid in 15 cms thick layers & well compacted for gutter & for hume pipe for which upto side half portion including curing etc. complete. CC 1:4:8	cum	3.00		
3	Providing and laying reinforced cement concrete pipe NP3 for culverts in position to required level and slope for culvert including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials , labour , curing,sand cushion covering etc complete as per specifications. Size of pipe- NP3 450 mm dia.	Rmt	18.00		
4	Filling in plinth with murum from selected earth brought from outside by spreading, watering,levelling and well consolidating in layers not exceeding 150mm thickness at a time etc. complete as directed.	Cum	786		
5	Earth work excavation using JCB including excavating,spreading,levelling of murrum etc complete as directed by EIC.	Hrs	5		
6	Providing & constructing brick masonry with approved quality of modular brick of standard size with necessary scaffolding, curing for basement & super structure in C.M 1:6	Cum	3		
7	Providing (12mm) plastering to internal surfaces including curing, scaffolding, rounding of all corners wherever required smooth rendering in CM 1:4 with 12 mm thick plaster.	Sqm	35		
8	Providing & fabricating mild steel/HYSD steel reinforcement including straightening cutting, bending, hooking, lapping or welding wherever required, placing in position tying with binding wire of approved quality & gauge including the cost of binding wire & anchoring to the adjoining members wherever necessary including all laps etc., complete as per design, specification & directions.	Kg	40		
9	Providing & laying cement concrete using 20mm & down size Granite or trap laid 15 cms thick layers & well compacted, vibrating, curing finishing, form work, centering etc., complete.				
	(a) RCC chamber cover C. C 1:2:4 (Exclusive of cost of steel & fabrication charges)	Cum	0.5		
10	Providing, fabricating & fixing M.S angles for chamber cover Including painting of two coats of oil paint over a coat of red oxide of approved brand & shade proper laying of the angle finishing with concrete/plaster etc complete as directed by EIC.	Kg	25		
	Total amount				

Contractor sign with seal

