

HLL LIFECARE LTD,KANGALA.

ANNEXURE

NAME OF WORK: Pavers & steps tiling at unipill plant.

Sl. No	Description	Unit	Qty.	Rate	Amount
1	Providing & laying Step tiles (thickness 20mm/ to be specified by the manufacturer) of 1st quality of approved colour & size on existing concrete flooring including dismantling of existing flooring to required slope & shifting of debris, laying in cement mortar (1:3), fixing of tiles by using cement slurry @ 4.4 Kg/Sqm and pointing the joints with coloured cement, cleaning, curing etc finishing for steps Tread, risers & landings. (Make-Ultra designer portfolio/equivalent)	Sqm	28.00		
2	Providing & laying heavy duty cobble stone 60mm thick interlock pavers, using cement and coarse sand for manufacture of block of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour, necessary excavation for levelling, concreting for edges and HOM of machineries complete as per specifications.	Sqm	480		
3	Earth work excavation for Foundation & removing the excavated earth outside as directed by Engineer-in-charge. Soft soil & Hard murum	Cum	30		
4	Earth work excavation for leveling & lowering the ground and removing the excavated earth to a distance as directed by engineer in charge including spreading, leveling, watering compacting in layers of 15 cms thick to the required slope using excavated earth (filling qty not to be measured & paid).	Cum	100		
5	Filling in plinth with murum from selected earth brought from outside by spreading, watering and well consolidating in layers not exceeding 150mm thickness at a time etc. complete as directed.	Cum	50		
	<b>Total amount</b>				

Contractor sign with seal