

MoHFW/HLL Lifecare Limited
CORRIGENDUM-01

Tender No. MoHFW /AIIMS-RISHIKESH/Ext El. /HLL/ID/2013
Sub:SETTING UP OF RESIDENTIAL COMPLEX AT AIIMS RISHIKESH
(SH: External Electrification Works)

Sl. No.	Queries / Clarifications	Reply /Clarification
1	Please specify the quantity of Astronomical switches in the feeder pillar is 4 or 1. However technically only 1 is required in outgoing of MCCB.	Only one is required in outgoing of MCCB in each feeder pillar
2	Feeder pillars require Contactor. If you require 4 nos. Astronomical switches then you require 4 nos. contactor also. Please specify.	Only one contactor is required in each feeder pillar. The cost of the Contactor shall be inclusive in the cost of Feeder pillar.
3	Please specify the size of i/c cable for feeder pillar required for termination or please make a different item for 7 nos. termination of i/c cable in feeder pillar.	The incomer cable sizes are as follows: 1. 3.5x 25 sq.mm – 5 nos. 2. 3.5x 50 sq.mm – 2 nos.
4	BOQ Item of FEEDER PILLAR at Sr. No. 1.10 is MODIFIED. The bidders are requested to quote considering the modified item.	Modified BOQ Item of FEEDER PILLAR at Sr. No. 1.10 is as follows "S/I/T/C of outdoor type feeder pillar, metal clad, suitable for 415 volt 3 phase 50 Hz with suitable foundation and arrangement for incoming/ outgoing cabling termination, earthing, locking arrangement , insulated aluminum bus bars system interconnection etc. (Ref. Figure no. 2 Clause No. 2.14 of CPWD electrical specification part 1 internal) Incoming : 60 Amp TP MCCB 25 kA - 1 Nos along with one no. 24 hrs Astronomical timer switch of L & T / Lagrand or equivalent make with necessary contactor Outgoing : 40 Amp DP MCB 10 kA - 4 Nos"

Note: Corrigendum shall form part of tender document.

End of Corrigendum-01

