

**RENOVATION AND MODIFICATION OF LECTURE HALL  
(INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD  
FLOOR AT JAC, JIPMER, PUDUCHERRY.**

**Volume- IV  
BILL OF QUANTITIES**

**Tender No: HLL/IDD/CHN/20-21/049**

**Dated: 31<sup>ST</sup> July 2020**



**HLL LIFECARE LIMITED  
(A GOVT. OF INDIA ENTERPRISE)  
JIPMER Campus, Dhanvantari Nagar,  
Puducherry – 605006  
Ph : 0413 - 2298295  
Web: [www.lifecarehll.com](http://www.lifecarehll.com)**

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

S. N	DESCRIPTION OF WORKS	UNIT	QTY	RATE IN FIGS IN RS.	RATE IN WORDS IN RUPEES	AMOUNT IN FIGS IN RS.
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)					
1.1	With cement mortar 1:4 (1 cement : 4 fine sand)	Sqm	61.095			
2	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum					

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

	board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :					
2.1	Fully Perforated Gypsum Plaster Board of size 1200 x2400x12.5 mm having approx. 15 % perforated area with perforation size and pattern as approved by the Engineerin-charge and as per manufacturer's specification, with all 4 side tapered and backed by acoustical tissue with NRC value not less than 0.60.	Sqm	82.928			
3	Filling the gap in between aluminium frame & adjacent RCC/ Brick/Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.					
3.1	Upto 5mm depth and 5 mm width	Metre	107.000			
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting					

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

	chases and making good the walls etc.					
4.1	25 mm nominal outer dia Pipes	Metre	40.000			
4.2	32 mm nominal outer dia Pipes	Metre	114.000			
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm	698.672			
6	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.					
6.1	Two coats	Sqm	889.912			
7	Cutting holes up to 30x30 cm in walls including making good the same:					
7.1	With common burnt clay F.P.S. (non modular) bricks	Each	16.000			
8	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform	Sqm	403.600			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

	etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineerin-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done.					
9	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:					
9.1	White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap	Each	1.000			
10	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931					
10.1	15mm nominal bore	Each	1.000			
11	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Each	1.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

12	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium Type PVC conduit with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sqmm, FRLS PVC insulated copper conductor single core cable etc. as required.					
12.1	Group C	Point	50.000			
13	Wiring for circuit/submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.					
13.1	2 x 2.5 sq.mm + 1x 2.5 sq.mm earth wire	Metre	600.000			
13.2	2 x 4 sq.mm +1x 4 sq.mm earth wire	Metre	550.000			
13.3	4 x 10 sqmm + 2 x 6 sqmm earth wire	Metre	120.000			
13.4	4 x 16 sqmm + 2 x 10 sqmm earth wire	Metre	620.000			
14	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

14.1	5/6 A switch	Each	23.000			
14.2	15/16 A switch	Each	30.000			
14.3	3 pin 5/6 A socket outlet	Each	23.000			
14.4	6 pin 15/16 A socket outlet	Each	30.000			
14.5	Telephone socket outlet	Each	1.000			
15	Supplying and drawing 2 pair, 0.5 sq mm FRLS PVC insulated copper conductor, un armoured telephone cable in the existing surface/recessed steel/ PVC conduit as required.					
15.1	2 Pair	Mtrs	620.000			
16	Supplying and drawing of UTP 4 pair CAT 6 LAN Cable in the existing surface/ recessed Steel/ PVC conduit as required.					
16.1	1 run of cable	Metre	620.000			
16.2	2 run of cable	Metre	160.000			
17	Supplying and fixing of Medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
17.1	25 mm	Metre	780.000			
17.2	32 mm	Metre	200.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

18	Supplying and fixing 2 modular stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	Each	30.000			
19	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	Each	15.000			
20	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.					
20.1	1 or 2 Module (75 mmX75 mm)	Each	3.000			
20.2	3 Module (100 mmX75 mm)	Each	30.000			
20.3	6 Module (200 mmX75 mm)	Each	17.000			
21	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	Each	108.000			
22	Supplying and fixing extra conduit down rod of 20 cm length G.I. pipe 15 mm dia, heavy gauge including painting etc. as required. (Note : More than 5 cm length shall be rounded to the nearest 10 cm and 5 cm or less shall be ignored)	Each	30.000			



**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

23	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)					
23.1	12 way, Double door	Each	1.000			
23.2	16 way, Double door	Each	1.000			
24	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/ Isolator)					
24.1	8 way (4 + 24), Double door	Each	2.000			
25	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
25.1	Single pole	Each	80.000			
25.2	Single pole with neutral	Each	12.000			
25.3	Triple pole and neutral	Each	4.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

26	Supplying and fixing following rating, four pole, 415 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
26.1	40 Amps	Each	6.000			
26.2	63 Amp	Each	2.000			
27	Supplying and fixing following rating, four pole, (three phase and neutral), 415 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required					
27.1	40 Amps	Each	6.000			
27.2	63 Amp	Each	2.000			
28	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 amps "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	Each	2.000			
29	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required.	Each	30.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

30	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	Mtr	65.000			
31	Supplying, installation, testing & commissioning of intelligent analog addressable photothermal detector complete with mounting base complete as required.	Nos	50.000			
32	Supplying, installation, testing & commissioning of intelligent addressable thermal detector with rate of rise cum fixed temperature thermistor complete with base as required.	Nos	2.000			
33	Supplying, installation, testing & commissioning of response indicator on surface/recessed MS Box having two LED, metallic cover complete with all connections etc as required.	Nos	25.000			
34	Supplying, installation, testing & commissioning of addressable manual call point complete as required. (Pull Type)	Nos	2.000			
35	Supplying, installation, testing & commissioning of intelligent addressable programmable sounder complete as required.	Nos	2.000			
36	Supplying & laying of 2x1.5 sqmm fire alarm armoured cable, 600/1000V rated with annealed copper conductor having XLPE insulation, steel wire armouring & FRLS outer sheath complete as required.	Mtrs	450.000			
37	Supplying, installation, testing & commissioning of fault isolator complete with base as required.	Each	4.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

38	Supplying, installation, testing & commissioning of 1.5/3/6W metal box ceiling/wall speakers complete as required.	Each	35.000			
39	Supply and Installation of Acoustics false ceiling of Anutone Subtex Nubby, square edge, Glassfibre core fully encapsulated ceiling tile of size 595x595x15mm having density 100-120Kgs/m3, weight 1.5-1.8kg/m2 which is suspended by using 0.3mm thick and 15mm wide pre coated metal T15 grid system. The T15 Grid system of 600x600mm module shall include wall angle (WA15W30) with unequal flanges of size 14&20mm wide, length 3000mm, 0.43mm thick fixed along the perimeter of walls with the help of nylon sleeves and suitable fasteners at 300mm centers. Then suspend the Main T15 (MT15W36) having flange width 15mm, height 32mm and length 3600mm from the soffit with help of soffit cleat and wire rod with leveling spring clip at 1200mm c/c. Cross T15 (CT15W12) having flange width 15mm, height 32mm and length 1200mm is then interlocked into the pre-cut slots in the Main T15 at 600mm centers in the direction perpendicular to the Main T15. Finally Cross T15 (CT15W06) having flange width 15mm, height 32mm and length 600mm are then interlocked into the pre cut slots in the 1200mm Cross T15 at 1200mm centers and in direction parallel to the Main T15. Subtex Nubby Square edge of size 595x595x15mm thick shall be placed into the grid size of 600x600mm. Ensure arrow marks behind subtex panels are oriented in one direction to achieve uniform shade. Technical Parameters Core - Glassfibre, Fire - Class 1 & P, Acoustics - NRC 0.9, Climate (OC RH) - 40, 95, Termite resistance - Yes, Light reflectance - 85 % , Green (RC %) - 35, Hygiene (VoC, Clean room) - Low, Class 3 ,Strength, Load capacity (Kg) - Antisag	Sqm	315.472			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

40	Supply & installation of Acoustical Wall Panels Anutone Synth Slim on strand panels of Anutone Slats made of pinewood fiberboard, Melamine laminated finish, groove perforated slats L16-2 - backlined with black acoustical fleece, tongue-groove edge for a seamless look, of size 128x2440x16mm thick having base density 800Kg/m <sup>3</sup> , weight 12Kgs/m <sup>2</sup> installed by using GI strut system. The GI strut system includes GI Cross channel (CC25) having thickness 0.55mm, length 3600mm, knurled web 50mm, depth 25mm and equal flanges 15mm is fastened vertically/horizontally at every 600mm centers. Aluminium core cross channel (CC18) having thickness 0.5mm, length 2400mm, web 15mm & 27mm, depth 18mm and flanges of 7mm with suitable edge & centre brackets is then fixed perpendicular to the CC10 with the help of fasteners at every 400mm centers. Slats of size 128x2430x16mm in then fixed perpendicular to CC18 with suitable edge & centre brackets. Contractor to provide expansion joints of 3mm at every 5mtrs bothways. Panels shall be backlined with acoustical infill of Anutone Synth PF 5x25mm thick adhered to the wall using Stick 7 adhesive. Technical Parameters : Core Variants - Pinewood E1 Fibreboard, Fire - Class 1 & P, Acoustics - NRC upto 0.75, Climate (OC RH) - 50, 70, Light reflectance - 75% (beech haya), Green (RC %) - 25, Hygiene (VoC, Clean room) - Low, Class 1, Strength, Load capacity (Kg) - Ball-Impact.	Sqm	113.360			
41	Supply and installation of Acoustical Wall Panels Anutone Synth Slim, polyfibre panels, core-pigmented, high-density, SynthPF rigid panels of size 1200x2400x9mm thk, volume density 210 - 230kg/m <sup>3</sup> , weight 1.9 - 2.1kg/m <sup>2</sup> installed by using Anutone Strut framework system. The Anutone Strut framework systems includes Anutone Strut CC25 Cross Channel					

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

	having thickness 0.55mm, length 3600mm, knurled web 50, depth 25mm and equal flanges 15mm is fastened to wall positioned horizontally in a regular manner at 600mm c/c. Anutone Strand, Square edge, Magnesite bonded pinewood fibre core tiles of size 600x2400x20mm, density 400 kgs/m <sup>3</sup> , weight 8kg/m <sup>2</sup> are fastened to Strut CC25 Cross channel with suitable fasteners. Longer edges of the panel should be perpendicular to Strut CC25 Cross Channel. Synth Slim Panels are then adhered to strand behind with stick S7 adhesive. The system is backlined with the acoustical infill Anutone SynthPF 10x25. Technical Parameters of Synth Slim Fire (Class) – B, Acoustics – NRC 0.4 (For A mounting), Thermal conductivity (W/mk)– na, Climate (°C, RH) – 50, 99, Light reflectance (%) – Colour Dependant, Green (VoC, RC %) – Nil, 30 ; Technical Parameters of Strand , Fire (Class) – 1 & P ,Acoustics – NRC 0.90 (For 25mm C50 Mounting), Thermal conductivity (W/mk)– 0.1, Climate (°C, RH) – 50, 95, Light reflectance (%) – 80, Green (VOC, RC %) – Low, 35.	Sqm	202.280			
42	Providing and fixing 100mm vertical blinds of approved colour made from 100% polyester yarn coated with fade resistant polymer to ensure complete opaquity with zero light transmittance having suitable coating on exterior, including all fixtures and fittings complete in all respect as per design and instructions of the Engineer-in-charge	Sqm	24.000			
43	Proving and fixing of Table with Material & Subtype: Engineered Wood - Particle Board Dimension (L)1050mm X (D)510mm X (H)750 with Matte Finish. Durian ComptonWorkspace Desk or equivalent as per approved make	Each	1.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

44	Supply and fixing of medium back chairs. Durian Jordon Mesh chair or equivalent as per approved make	Each	7.000			
45	Making Core Cutting in walls / slabs / beams / retaining walls and any other R.C / Brick members to following dia & depth by using suitable machine with tolerance for any type of inserts, pipes etc. Rate shall include for all charge, preparation of surface, cutting of reinforcement, cleaning the surface, staging, scaffolding application with necessary tools and equipments wat(lr and power, removal of debris from the site.					
45.1	150mm to 250mm dia to the following depth:	Each	5.000			
46	Supply and fixing of approved quality 3 seater steel chair with wooden study table.	Each	10.000			
47	Proving and fixing of Table with Material & Subtype: Engineered Wood - Particle Board Dimension (L)1900mm X (D)900mm X (H)750mm with Matte Finish. Durian Turin Wooden Conference Desk or equivalent as per approved make	Each	1.000			
48	Removing and reposition of existing aluminium windows approx. size of 2.65x1.75mts with MS grills. The work shall include removing of glaze from windows, removing aluminium sections/frames, refixing of windows to adjacent with necessary screws, refixing of new glaze, supply and fixing of rubber beading wherever required and all complete as per instruction of engineer-in charge.	Each	4.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

49	Supply and fixing of 10'x4' green board with dust collector and duster & chalk holder. The board frame have anodized extruded Aluminium alloy hollow section of designation 63400 conforming to IS: 1285, back cover galvanized steel sheets conforming to IS:277, and all complete as per instruction of engineer-in charge.	Each	1.000			
50	Removing the old light fixtures / ceiling fans and kept in safe custody inside the campus wherever JIPMER instructed (with in JIPMER campus)	Each	95.000			
51	Supply of 600 X 600 mm recess mounted Square LED 36 W down light in die-cast aluminium housing including high efficiency diffuser provides soft glare free light, driver etc including all required mounting accessories complete.	Each	40.000			
52	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. Data socket (RJ-45)	Each	8.000			
53	Supply, Installation, Testing, Commissioning of LED strip 22W along with drivers and all accessories, etc all complete (Havells FLEXION LED STRIP 22 W or equivalent as per approved make)	Mtr	160.000			
54	Supply of 3W deep spot LED light including all required accessories complete. (Havells LHEEBCPFUN1W003 or equivalent as per approved make)	Nos	68.000			
55	Removing of existing biometric device/CCTV system, and keeping in safe custody, and refixing the same on wall panel with supplying and drawing wiring wherever required and installing, testing & commissioning and etc all complete. in coordination with existing vendor	Job	1.000			



**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

56	Supply Installation, testing and commissioning of ultra short throw LCD projector 3200 ANSI lumens, WXGA (1200X800 PIXELS) 10000 hour lamp life and complete. EPSON EB-675Wi/equivalent as per approved make	Each	2.000			
57	Supply Installation, and commissioning of Motorised Projector Screen of size 9'x12' with all fixing accries.make: Alkosign/Abroad/equivalent as per approved make	Nos.	2.000			
58	Supply Installation of 15m HDMI Male to Male Cable kit.	Each	3.000			
59	Supply Installation of 15m VGA Cable kit.	Each	3.000			
60	Supply Installation, testing and commissioning of wireless hand microphone. Make: AKG/equivalent as per approved make	Each	2.000			
61	Supply Installation, testing and commissioning of 240W amplifier. Make: Bosch PLE-1ME240IN/equivalent as per approved make	Each	1.000			
62	Supply Installation, testing and commissioning of Yamaha MG16XU/equivalent as per approved make	Each	1.000			
63	Supply Installation, testing and commissioning of 22U rack of approved make.	Each	1.000			
64	Supply Installation, testing and commissioning of 24 port switch. Make: CISCO SG350 - 28 - K9 - EU/equivalent as per approved make	Each	1.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

65	Supply Installation, testing and commissioning of SFU Module	Each	2.000			
66	Supply Installation, testing and commissioning of Jack panel	Each	1.000			
67	Supply, laying & termination of 12 core ofc cable	Each	60.000			
68	Supply, installation of SC - LC OFC patch cord	Each	2.000			
69	Supply Installation, testing and commissioning of SC pigtail	Each	24.000			
70	Supply Installation, testing and commissioning of 12 Port LIU fully loaded	Each	2.000			
71	Supply Installation, testing and commissioning of 12U rack of approved make.	Each	1.000			
72	Supply, laying & termination of Cat 6 patch cord 2mtr	Each	24.000			
73	Supply, installation, testing and commissioning of following types of extinguisher with provision of wall bracket (fixed with anchor fastner) or floor mounted.					
73.1	ISI marked (IS:15683) Fire Extinguisher, Carbon-di-oxide type capacity 4.5 Kg. Flat base including valve, discharge hose of not less than 10 mm dia, 1M long and complete in all respects including initial fill with CO2 gas conforming to IS:307-1966 filled to a filling rate of not more than 0.667 and wall suspension bracket	Nos	2.000			

**BILL OF QUANTITIES****TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020****NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.**

73.2	ABC (Powder Type) Fire Extinguisher. In HP Mild Steel Cylinders ISI marked fitted with pressure indicating gauge, internal tube, squeeze lever type valve fully charged with ABC powder (Mono Ammonium Phosphate) pressured by Nitrogen complete in all respects including wall suspension bracket and conforming to IS:15683 4 Kg with pressure gauge squeeze grip type	Nos	2.000			
74	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required :					
74.1	25 mm dia	Mtrs	90.000			
74.2	32 mm dia	Mtrs	60.000			
74.3	65 mm dia	Mtrs	17.000			
74.4	80 mm dia	Mtrs	25.000			
75	Providing, fixing, testing & commissioning of 15mm dia quartzoid bulb type sprinklers of rating 68 degree centigrade with required accessories :					
75.1	Pendent Sprinkler	Each	23.000			
75.2	Upright Sprinkler	Each	23.000			

BILL OF QUANTITIES						
TENDER NO: HLL/IDD/CHN/20-21/049 DATED 31.07.2020						
NAME OF WORK: RENOVATION AND MODIFICATION OF LECTURE HALL (INCL CIVIL, ELECTRICAL, AV SYSTEM & FIRE) IN THIRD FLOOR AT JAC, JIPMER, PUDUCHERRY.						
76	Supplying, installation, testing & commissioning of sprinkler flexible pipe (UL Listed) of stainless steel complete with 15 NPT on reducer thread with maximum working pressure of 175 PSI test pressure of 875 PSI (Burst) with branch line (Inlet) 25mm NPT male thread to sprinkler head (Outlet) 15mm NPT female thread with reducer, nipple, 2 side brackets, center bracket, stockbar of following sizes complete as required.					
76.1	1200mm	Set	23.000			
Total Amount						
Add GST @12%						
Grand Total Amount incl. of GST@12% in Figures						
Grand total amount in words: Rupees						

1. The entire area must be made good after completion of works.
2. Damages caused to the existing property should be rectified at own risk and cost.
3. Measurements will be based on actual execution at site.

**END OF VOLUME - IV**