

HLL LIFECARE LTD,KANAGALA					
ELECTRICAL ENGINEERING DEPARTMENT					
The Electrification for primary packing false ceiling					
Sl. No	Work description	Unit	Qty	Rates	Amount
1	Supply of clean room luminaries: Model: 2' clean room with MiroReflector, Wattage:2*18W CFL CAT Ref: CRFW12218EB(300) Recessed mounted IP65 bottom openable clean room luminaire with SS frame. ,Make Cromton Greeves	No	12		
2	Installation of clean room luminaires lighting in false ceiling by using support of 6 mm GI rod with fastener anchor hooks (ceiling fan hanging hooks) with up and down adjustment from ceiling, The sets should be fixed by fixing supporting rods with threading and jointing nut and bolts etc.	No	12		
3	wiring of proposed power points by 2.5sqmmX3run,PVC insulated multistrand copper wire of FR grade of conforming to IS:694-1990 in 3/4 inch PVC conduit in concealed or above false ceiling with earthing bare copper wire of 12SWG.	meter	50		
4	Wiring of proposed lighting points/ by 1.5 sq.mm X 3 Run, pvc insulated multistrand copper wire of FR grade of confirming to IS:694-1990 in 3/4 inch PVC conduit with light points to switch board point in concealed/ above false ceiling.	meter	200		
5	Supply,installation & commissioning of ceiling fan of 230 volt,Make:USHA/Crompton greeves, deluxe model With heavy duty sweep size 1200 mm,with hanging 2 feet length suitable dia of 2 mm thick G.I pipe from top of roof to necessary height ( 9 ft from bottom)	Nos	9		
6	Supply of modular Type switch board with concealed GI METAL BOX and cover plate with following item. a) SP MCB of 10 amp- 1No for phase control, Anchor make , "B"eries b) modular type switches of 6A, 230V,-7No, Anchor make b) modular type FAN REGULATOR(5 STEP TYPE DIMMER), Anchor make -3 NO c) Modular type Plug in socket and plug top of 5 amp 230 VAC-1no , Make:Anchor	set	3		
7	Installation and commissioning of switch board panel with flush mounting to wall as suitable to GMP type and finishing to be made by civil and paint works as match to existing wall.	set	3		
<b>TOTAL AMOUNT IN RS</b>					

**Contractor sign with seal**

