

HLL LIFECARE LIMITED
(A Government of India Enterprise)
Projects Division
Corporate Head Office, Poojappura.P.O,
Thiruvananthapuram – 695012,
Kerala, India
Phn: 0471- 2354949, 2775588

AMENDMENT No. 1

Sub: Amendment Notice - Supply, Installation, Testing and Commissioning of Ductable Split Air Conditioning Units as per the Technical Specifications enclosed at HINDLABS MRI Centre, Government Medical College, Thrissur - reg.

Ref: Our IFB Ref No: HLL/CHO/PROJ/HCS/MRI-TCR/AC/2018-19 dated 17.11.2018.

Amendment Date: 23-11-2018

With reference to the above, following are amended

1) The scheduled date for receipt and opening of bids is hereby amended as follows.

- | | |
|---|--------------------------------------|
| a) Date of issue of tender document | - 17-11-2018 onwards |
| b) Last date and time for receipt of bids | - 07-12-2018 up to 15.00 Hrs. |
| c) Date and time of opening of Technical bids | - 07-12-2018, 15.30 Hrs. |

2) **Schedule II - Specifications** is amended and attached herewith.

All other terms and conditions of the tender remain unchanged.

SENIOR MANAGER (PROJECTS)

SCHEDULE V

PRICE SCHEDULE - AMENDED

Note: The bidders shall quote all the price schedules (Schedule V-A, V-B and V-C) and same will be considered for selection. Incomplete price schedules will not be considered for evaluation.

SCHEDULE V - A					
SCHEDULE OF WORK					
Sub:	Supply, Installation, Testing and Commissioning of Ductable Split Air Conditioners at HINDLABS MRI Centre, Government Medical College, Thrissur – reg.				
SI No	Item Description	Qty	Unit	Rate in Rs	Amount in Rs
1	Removing of existing light weight false ceiling tiles (60x60cm gypsum tiles) and aluminium grid framework for the installation of ceiling mounted ductable split AC units and its insulated ducts as required, refixing of the same false ceiling tiles and grids in proper line, level and finish etc. complete as directed by HLL Engineer-in-charge				
a)	MRI Gantry Room (Size: 20 feet x 12 feet), Existing false ceiling at a height of approx. 10 feet.	1	Job		
b)	Equipment Room (Size: 14 feet x 12 feet), Existing false ceiling at a height of approx. 9 feet.	1	Job		
2	SITC of 8 TR (Minimum) Inverter Ductable AC unit consisting of hermetically sealed high efficiency scroll compressor, Corrossion Resistant Copper Refrigerant Gold Fin coils, Brush Less DC fan motor assembled in powder coated metal enclosure with HP/LP safety switch, Electronic Expansion Valve, microprocessor based control unit, protection relays, contactor etc. Suitable for operating on R 410A / R407C gas complete air cooled compressor with accessories conforming to NABH standards. AC units shall be installed with suitable insulated ducting with supports, diffusers, dampers, bellows and suitable thickness under-deck insulation with nitrile rubber to prevent cooling loss, electrical connections etc complete.	2	Set		
TOTAL					
APPLICABLE GST					
TOTAL AMOUNT IN RS					

(RUPEES IN WORDS)

SIGN AND SEAL OF BIDDER

SCHEDULE V - B

Sub:	COMPREHENSIVE AMC FOR 10 YEARS INCLUDING WARRANTY PERIOD - REG.						
SI No	Item Description	CAMC Rate/Unit in Rs/Year					
		(inclusive of all applicable taxes)					
		1 - 5 years	6th Year	7th Year	8th Year	9th Year	10th Year
1	Ductable Split Air Conditioning unit at HINDLABS MRI Centre, Government Medical College, Thrissur	Free of Cost					
Total CAMC Amount for 2 Sets for 10 Years in Rs (inclusive of taxes)							
<p>Formula for evaluation of price bids and arriving the L1 (lowest price) is as given below: $L = (\text{Total AC unit cost} \times 0.90) + (\text{Total CAMC Cost} \times 0.10)$</p>							

SEAL AND SIGN OF BIDDER

SCHEDULE V - C					
SCHEDULE OF BUY BACK ARRANGEMENT					
SI No	Item Description	Qty	Unit	Rate in Rs	Amount in Rs
1	Removing existing ductable split AC units (Indoor and Outdoor units) including all allied connections etc complete as in actual site condition and Buy back of these AC units (Indoor and outdoor units complete) in AS IS WHERE IS basis	2	Sets		
TOTAL					
TOTAL AMOUNT IN RS (inclusive of applicable taxes)					

SIGN AND SEAL OF BIDDER

Note:- The Bidder shall visit the site and inspect the site and equipments before quoting for the same.