

Addendum - 1

Tender No: **PUR/08/R1/PQ/TRANSFORMER-INSTALLATION/2013-14** dated **20/12/2013**

Name of Tender – **INSTALLATION, TESTING & COMMISSIONING OF 1 NO, 1250 KVA, OUT DOOR, OIL FILLED, ONAN, 11KV OLTC TRANSFORMER AND ALL RELATED AUXILIARY UNITS at HLL LIFECARE LTD, Peroorkada-05**

The following is issued as an addendum in the tender details for the above mentioned work.

Correction No1, In Page No.32

5.5.1 MCCBs shall be of **three** pole **(TPN)** construction for panel mounting, operating mechanism shall be trip free...

Correction No2, In Page No.35

5.12.5 A **24Volts** DC power supply feeders shall be provided for each switchgear from Owners DC UPS...

Correction No3, In Page No.54

1.6.1 Supply, installation, Testing & commissioning of 2000 Amps, TPN AL-bus bar duct(**Sandwich Type**) having a minimum gross cross sectional area of 2000sqmm per phase (joining portion shall be tinned) made out of suitable rating high conductivity electrolytic **Aluminium** suitable for 500 volts, 50 Hz, 3 phase and neutral...

Correction No4, In Page No.29

5.3.1 The Busbars shall be made of Electrolytic grade high conductivity **Copper** with continuous rating as specified by HLL...

*All corrections are underlined & bolded for easy identification.

Joint General Manager (Purchase)

HLL Lifecare Ltd

Peroorkada Factory- 695005