

HLL Lifecare Ltd, KANAGALA

ANNEXURE

Name of the work-Car parking extension.

Sl. No	Description	Unit	Qty	Rate	Amount
1	Earth work excavation for Foundation & levelling removing the excavated earth to a distance not exceeding 50 M with a lift up to 1.50 m including refilling of excavated earth wherever required.	Cum	29		
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms. thick, well compacted, in foundation, including cost of all material, labour, HOM of machinery, curing complete as per specifications.	Cum	3		
3	Structural Steel (MS Pipes) work riveted, bolted or welded in built up sections, trusses & framed work for car shed including cutting hoisting, bending fixing in position & applying priming coat of approved steel primer with two coats of oil paint all complete.	Kg	980		
4	Providing & laying granite or basalt or trap jelly cement concrete (1:3:6) using 20 mm& down size jelly including mixing, laying, tamping, curing & smooth finishing using cement slurry for exposed faces & with necessary centering & form work etc., complete. Sills & coping & any other such works.	Cum	19.5		
5	Supplying and filling in plinth with Murum/ Earth under floors including, watering, ramming consolidating and dressing complete	Cum	40		
6	Providing & fixing pre colour coated bent to required profile GI sheets of 0.50 mm thick of approved make all these sheets to be fixed to purling using self tapping screws , EPDM seal, metal washer, including labor, bending fixing new sheets etc complete. (Make-TATA/Jindal)	Sqm	110		
	Total amount				

Contractor sign with seal