

H.L.L.KANAGALA					
ELECTRICAL ENGINEERING DEPARTMENT					
Estimation for Wiring of toilets at police station Sankeshwar					
sl.no	Work detail	UNIT	QTY	RATE RS	AMOUNT RS
1	Supply, installation and commissioning of 6 way, sheet steel, double door horizontal type MCBDB with common neutral bus bar, earth bus bar, din bar detachable gland plate, interconnections with powder coated paint. Make: Hager/indoasian/stanley. INCOMING: DP MCB of 16 amps = 1 no Out Going: Single pole MCB of 10 amp = 4 no for lighting and Exhaust fan circuit .	No	1		
2	Wiring for lighting/fans in casing and capping of 25mm size along with 1.5 sqmm X 2 run + 1.5sqmm X 1 run (earthing) with Color code of Red for phase, Black for neutral and green for earthing. The separate circuit should be provided for each switch boards from MCB DB	Meter	50		
3	Supply and commissioning of fluorescent tube light set. Model: CAT REF: T5JB13114EB LAMP TYPE 1X 14 W T5 , Surface mounted slim decorative box type luminaire with CRCA housing and decorative end caps. Make: Crompton Greeves/equalent	No	4		
4	Supply and commissioning of outdoor luminaire. Model: CAT REF: SCE 1209 wattage 1 x 9 watt CFL Decorative CFL streetlight luminaire with MS housing finished in bright red And having clear acrylic cover. Make: Crompton Greeves/ equalent	No	1		
5	Supply, fixing and commissioning of ceiling rose for light/fan points. Make: Anchor	No	9		
6	Supply, Installation and commissioning of Exhaust fan Ventilator DX Sweep : 150mm, RPM: 1300 Air displacement in cubic meter/Hr: 480. Consumption in watt: 30 International design with metal shutter to prevent entry of foreign materials. Make: Orient/Crompton/Polar	No	3		
7	Supply, installation and commissioning of surface mounting modular switch boards with Switch-5 amp-5 No, Plug socket of 5 amps - 1 No, Make: Roma (Anchor) Modular switch, socket and metal box with plate.	No	2		
	Total amount				

Contractor sign with seal.

SUMMARY

1) Civil works Rupees. ----

2) Electrical works Rupees. ----

Total amount

