

SCHEDULE OF QUANTITIES

MODIFICATION WORKS OF AMRIT PHARMACIES AT					
PART I - LADY HARDINGE MEDICAL COLLEGE, NEW DELHI					
SL. No	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes
1	P/F of Prelaminated Over head Storage unit of size 1200x750x450mm made out of 25mm thick prelam MDF board top PVC edge-binding as/design 18mm thick prelam MDF board hinged shutter with laminate and handle with individual locks.6mm thick laminated ply as backing of the unit along with 18mm thick prelam board as adjustable shelves.	Sqm	8.00		
2	P/F storage unit 350mm deep laminated with 18mm thk laminated shelves. The storage unit to be fixed between two 150mm wide laminated fascia 300mm wide 12mm thk toughened glass shelves to be fixed with self supports and adjustable holders till 1800mm complete as per design intend.	Sqm	9.50		
3	Providing and fixing metallic ceiling at entrance lobby complete as directed.	Sqm	8.00		
4	Shifting of two nos of existing CCTV Camera complete in all respect as directed.	Job	1.00		
5	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	5.75		
	Total				

PART II - Dr. RAM MANOHAR LOHIA HOSPITAL, NEW DELHI					
SL. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes

1	Providing and fixing 1.0mm thick GI Gutter along with rain water pipe to existing structure complete in all respect.	Rmt	9.00		
2	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	8.45		
Total					

PART III - SAFDARJUNG HOSPITAL, NEW DELHI

SL. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes
1	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	7.50		
Total					

PART IV - AIIMS, NEW DELHI

Sl. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes

1	P/F of Double level Counter of 750mm depth and Counter top at 1050mm level 275 mm wide 12mm thick Korean acrylic sheet to be used for counter top on 25mm thk commercial ply 12mm thk "L" shaped laminated strip of 150x200mm to be fixed with 12mm thk ply at 850mm. Display unit with 8mm thick toughened glass fascia and 18mm thick Prelaminated shelf's to be inbuilt in counter with movable shutter. Under counter shortage unit to be fixed with individual locks and handles as per app. 150mm high SS glossy skirting. 600mm wide laminated door and open able counter top to be part of the counter as per design. Provision to be made for fixing Cash Locker supplied by client. Make: Greenlam-173 Barbie Pink, 283 Sky Blue/LG Hausys-G019 Natural Quartzes/Equivalent	Sqm	8.23		
2	P/F 19mm thick commercial board covered with 2mm thick Polyflor Vinyle above the medicine storage complete as directed.	Sqm	16.00		
3	Removing and refixing existing laminate to match the colour scheme complete as directed.	Sqm	30.00		
Total					

PART V- AIIMS, BHOPAL

SL. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes
1	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	10.69		

2	Supplying of minimum 36 watt LED recessed type (600 mmx600mm) extruded aluminum luminaries with heat sink installed back side, high quality diffuser fix in front frame max depth of 10mm total system wattage less than 45W with LED make of Cree/Nichea (36x1W LED) operating at 350 mA. lamp color 4000k, complete with electronic driver, CRI 80, lamp life 50,000 hrs, warranty 5 years, lockable holders and including connection etc. as required, similar to Bajaj make BGRSQL 3601 WH or GE Troffer or Vivo LED.	Each	4.00		
Total					

PART VI - AIIMS, RISHIKESH

SL. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes
1	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	6.00		
Total					

PART VII - NEHRU HOSPITAL, PGIMER, CHANDIGARH

SL. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes
1	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	6.00		
Total					

PART VIII - ADVANCED CARDIAC CENTRE, PGIMER, CHANDIGARH					
SL. No.	Description	Unit	Qty	Rate (INR)	Amount (INR) - incl. of all taxes
1	Providing and fixing 12mm thick frameless toughened glass above the existing counter of approved sizes and of approved manufacturer including P/F SS bracket top to hold the glass and 6" dia hole all complete as per direction of Engineer-in-charge.	Sqm	10.00		
	Total				
	GRAND TOTAL				