

HLL BIOTECH LIMITED							
INTEGRATED VACCINES COMPLEX, Chengalpattu							
nne pharmaplan®	Document Name:		Data Sheet for Air Cooled Brine Chiller - Cold Rooms			 HLL BIOTECH LIMITED <small>Subsidiary of HLL Lifecare Limited (A Government of India Enterprise)</small>	
	Data Sheet No.		NPI/120310/DS/U/CHB 01/02/03				
	Date / Revision		2014.05.08/ 01				
ACCESSORIES / SAFETIES / INTERLOCKS							
52	Relief valve	Required	60	Control Panel	Required		
53	Drain valve	Required	61	(System ON / OFF)	Required		
54	Air vent	Required	62	Solenoid valve	Required		
55	Motor overload relay	Required	63	Sensor Calibration	Required		
56	Power on Indicator	Required	64	Flow monitor	Required		
57	Stop valve	Required	65				
58	Motor over current	Warning / cut off	66				
59			67				
DATA TO BE TRANSFERRED FROM MICROPROCESSOR TO BMS							
68	Chilled brine in & out temp.	Required	74	Chiller trip status	Required		
69	Condenser refrigerant temp.	Required	75	Chiller brine flow status	Required		
70	Evaporator refrigerant temp.	Required	76	Chiller ON/OFF	Required		
71	Chiller RUN status	Required	77				
72	Cooling Water in & Out temp.	Required	78				
73			79				
MICROPROCESSOR OPERATION DETAILS							
80	Control system start up sequence	Required	85	Failure reset	Required		
81	Unload at start	Required	86	Chiller stop sequence	Required		
82	Failure detection and recovery	Required	87	System is enabled after satisfying permissive interlock like flow switch	Required		
83			88				
84							
SPECIFIC POWER CONSUMPTION							
89	Sp.power consumption at inlet Cooling water temperature.		90	Sp.power consumption at part load			
	34 Deg C	XX KW/TR		100%	XX		
	33 Deg C	XX KW/TR		90%	XX		
	32 Deg C	XX KW/TR		80%	XX		
	31 Deg C	XX KW/TR		70%	XX		
	30 Deg C	XX KW/TR		60%	XX		
	29 Deg C	XX KW/TR		50%	XX		
	28 Deg C	XX KW/TR		40%	XX		
	27 Deg C	XX KW/TR		30%	XX		
	26 Deg C	XX KW/TR		20%	XX		
	25 Deg C	XX KW/TR		10%	XX		
	24 Deg C	XX KW/TR					
	23 Deg C	XX KW/TR					
	22 Deg C	XX KW/TR					
	21 Deg C	XX KW/TR					
	20 Deg C	XX KW/TR					
PERFORMANCE							
91	Performance check		92	Target performance			
	Total refrigeration generation	XX TR		Sp.power consumption (Max)	0.9 KW/TR at duty condition		
	Motor power consumption	XX TR					
	Condenser heat rejection	XX TR					
	Deviation	XX TR					
SCOPE OF SUPPLY OF VENDOR							
93	First charge of refrigerant	Vendor's scope	101	Transportation from stores to exact location within site	Vendor's scope		
94	First charge of oil	Vendor's scope	102	Errction & commissioning at site	Vendor's scope		
95	Isolation pads	Vendor's scope	103	Performance testing at factory	Vendor's scope		
96	Holding down/Foundation bolts	Vendor's scope	104	Commissioning spares	Vendor's scope		
97	Consultation for chiller vendor to mention insulation material and thickness to be used for chiller pads	Vendor's scope	105	2- year & 5 year running spares	Vendor's scope		
98	Painting	Vendor's scope	106	Material handling equipments	Vendor's scope		
99	Victaulic coupling for chilled BrineInlet & outlet	Vendor's scope	107	Coordination with client while commissioning the chiller at site	Required		
100							
NOTES							
1)	The chiller equipment shall be complete with necessary pipings, isolation valves, control panel, sequence timer, control valves, pressure / temperature instruments, relief valves,solenoid valves, auto drain valves, safety interlocks, alarm hooters, etc.						
2)	All valves shall be supplied with relevant test certificates.						
3)	All instruments shall be supplied with relevant calibration certificates & traceability certificate from reputed Testing Lab.						
4)	Asbestos based gasket material is prohibited.						
5)	Vendor should mention makes of all components.						
6)	Vendor should submit the DQ, IQ & OQ documents to the client.						
7)	Communication port suitable to connect to the central BMS system to be provided						
PRE-DESPATCH / INSPECTION DOCUMENTS REQUIRED							
1)	Complete operational test of the unit with FAT protocol						
2)	Operational and Maint. Manual in 3 set						
3)	GA drawing						
4)	Electric circuit diagram						
5)	Control logic						
6)	Dimensional drawing indicating size and location of nozzles						
7)	As built drawings						
8)	List of fast moving spares with part nos						
9)	Material test certificates						
10)	Foundation detail drawing						
AFI -- Approved for enquiry, AFO -- Approved for ordering							
01	2014.05.08	VSHI	SMBY	HLL/PIIC	<input checked="" type="checkbox"/>	<input type="checkbox"/>	sheet:
Rev.	Date	Prepared by	Checked by	Approved by	AFI	AFO	2 / 2