

**HLL LIFECARE LIMITED, KANAGALA
ANNEXURE**

WORK : Concrete flooring for BDU shed.

Sl. No	Description	Unit	Qty	Rate	Amount
1	Earth work excavation for Foundation & removing the excavated earth outside as directed by Engineer-in-charge. Soft soil & Hard murum	Cum	15		
2	Providing & laying Granite or Basalt or trap jelly concrete using 40 mm & down size jelly for foundation laid in 15 cms thick layers & well compacted including curing etc complete. Cement concrete 1:4:8.	Cum	3.5		
3	Providing and constructing uncoursed stone Masonry in 1:6 cement mortar in foundation & plinth with bond stones (2 m apart) and rough quoin stones including curing, pointing etc. complete as directed.	Cum	19		
4	Providing and filling in plinth with hard murrum brought from outside including spreading, leveling, watering compacting in layers of 15 cms thick to the required slope etc complete as directed by engineer in charge.	Cum	100		
5	Providing & laying granite or basalt or trap jelly cement concrete (1:3:6) using 20 mm & down size jelly including mixing, laying, tamping, curing & smooth finishing for exposed faces & with necessary centering & form work etc., complete. Sills & coping & any other such works.	Cum	45		
6	Providing (12mm) plastering to internal surfaces including curing, scaffolding, rounding of all corners wherever required smooth rendering in CM 1:4 with 12 mm thick plaster.	Sqm	500		
7	Providing & constructing brick masonry with approved quality of modular brick of standard size with necessary scaffolding, curing for basement & super structure in C.M 1:6	Cum	12		
	Total amount				

Contractor sign with seal

