

**HLL LIFECARE LIMITED, KANAGALA****Annexure****WORK : Repairs of Concrete flooring at Latex store.**

<b>Sl. No</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1	Earth work excavation for Foundation & removing the excavated earth outside as directed by Engineer-in-charge.Soft soil & Hard murum	Cum	5		
2	Dismantling of existing cement concrete with steel & disposing the debris outside as directed by Engineer-in-charge.	Cum	25		
3	Providing & laying cement concrete 1:2:4 using 20mm & down size Granite or trap laid 10 to 15 cms thick layers & well compacted, vibrating, curing finishing, form work, centering etc., complete.				
	(a) For foundation	Cum	25		
4	Providing (12mm) plastering to internal surfaces including curing, scaffolding, rounding of all corners wherever required smooth rendering in CM 1:4 with 12 mm thick plaster.	Sqm	180		
5	Providing & fabricating mild steel/HYSD steel reinforcement including straightening cutting, bending, hooking, lapping or welding wherever required, placing in position tying with binding wire of approved quality & gauge including the cost of binding wire & anchoring to the adjoining members wherever necessary including all laps etc., complete as per design, specification & directions.	Kg	430		
	<b>Total amount</b>				

**Contractor sign with seal**