

## HLL Lifecare Ltd, KANAGALA

### ANNEXURE

#### Name of the work-Shed for Bulk Drug store

SI.No	Description	Unit	Qty	Rate	Amount
1	<b>Earth work excavation</b> for Foundation & levelling removing the excavated earth to a distance not exceeding 50 M with a lift up to 1.50 m including <b>refilling of excavated</b> earth wherever required.	Cum	5		
2	Providing & laying granite or basalt or trap jelly cement concrete (1:2:4) using 20 mm & down size jelly including mixing, laying, tamping, curing & smooth finishing for exposed faces & with necessary centering & form work etc., complete. Sills & coping, foundation & any other such works.	Cum	10		
3	Providing, fabricating & fixing M.S angle/pipes/MS squares/bolts 6mm thick, ISLC 100X50X6/5, 75x40x6/5, 65X65X6/5, 50X50X6/5, MS plate with anchor bolts for roofing structure. Including painting of two coats of oil paint over a coat of red oxide of approved brand & shade with making necessary holes in the masonry/ concrete & proper laying of the angle finishing with concrete/plaster etc complete as directed by EIC.	Kg	2925		
4	Providing & fabricating mild steel/HYSD steel reinforcement including straightening cutting, bending, hooking, lapping or welding wherever required, placing in position tying with binding wire of approved quality & gauge including the cost of binding wire & anchoring to the adjoining members wherever necessary including all laps etc., complete as per design, specification & directions.	Kg	200		
5	Providing & fixing pre coated profile GI sheets/ridges of 0.45 mm thick of approved make all these sheets to be fixed to purling using self tapping screws or J-hooks, EPDM seal, metal washer, including labor, fixing new sheets etc complete.	Sqm	250		
	<b>Total amount</b>				

Contractor Sign with seal