

HLL LIFECARE LTD KANAGALA.					
ELECTRICAL ENGINEERING DEPARTMENT					
ANNEXURE					
Sl. NO	Work description	UNIT	qty	RATE in Rs	AMOUNT in Rs
1	<p>Suplly, installation and commissioning of Borewell Panel. The panel should be suitable size of 16 gauge GI sheet with suitable locking provision along with following equipments.</p> <p>Specification:</p> <p>1. FN (TPN) S-D-F suitable for DI in SS enclosure of 32 amps 415 volt, ,CAT No- SK95613 Make:L&T with HF fuses of 25amps for main incoming-1 No.</p> <p>2. submersible Pump Controller in Sheet enclosure Type FOR 7 HP Relay range, MU-G10 DOL starter Cat No- SS95983 -Make:L&T -1 No.</p> <p>3. One CFL lamp of PL-11watt with holder and control switch.</p> <p>The Panel should be fixed and commissioned at 1.5 meter height from ground with suitable supports (MS Pole) after inspection and approval of Electrical -in charge.</p>	No	1		
2	Suplly, laying and commissionin of 3 Corex 4 sqmm Flat flexible cables Make: polycab/Finolex/havells for sebmersible pump	meter	130		
TOTAL AMOUNT IN RS					

1 Drilling work (A+B) ----
2 Electrical (C) ----
Total amount

Contractor sign with seal