

Amendment No:1

to

Tender no. : HITES/IDS/16/07/JIPMERII/KIK-05/LF/2016-17 Dated: 24.06.2016

for

Supplying, installation and commissioning of lab Furniture

at

JIPMER II Campus at Karaikal.

The following amendments are incorporated in the referred tender enquiry document:

In SECTION – VI: LIST OF REQUIREMENTS

For:

Part II: Required Schedule & Part III: Scope of Incidental Services:

Within **45 days** from date of Notification of Award or handing over of the site by engineer In-charge, whichever is later. Delivery, design, Installation & Commissioning, Supervision, Demonstration, Trial run and Training etc. as specified in GCC Clause 13. The delay on the part of the supplier to install and commission the equipment will attract the provisions as contained in the liquidated damage clause.

Read As:

Part II: Required Schedule & Part III: Scope of Incidental Services:

Within **60 days** from date of Notification of Award or handing over of the site by engineer In-charge, whichever is later. Delivery, design, Installation & Commissioning, Supervision, Demonstration, Trial run and Training etc. as specified in GCC Clause 13. The delay on the part of the supplier to install and commission the equipment will attract the provisions as contained in the liquidated damage clause.

In Technical specification:

As per Tender Specification	Amended As
<p><u>Specification of frame work</u> The frame shall be of rectangular box with a wall thickness of 12gauge, de – greased and powder coated for smooth finish and protection.</p> <p>The dimension details of frame work is Vertical member of minimum 60x40mm ,Horizontal top member 50x40mm &Horizontal bottom member 80x40mm</p>	<p><u>Specification of frame work</u> The frame shall be of rectangular box with a wall thickness of 14 gauge or better, de – greased and powder coated for smooth finish and protection.</p> <p>The dimension details of frame work is Vertical member of minimum 60x40mm ,Horizontal top member 50x40mm &Horizontal bottom member 80x40mm (minor variation in dimensions are acceptable providing that weight carrying capacity of worktop should be 250 kgs/metre or better)</p>
<p>Added para:</p>	<p>Bidder shall be responsible for complete installation and commissioning of the laboratory workbenches on turnkey basis including electrical wiring, plumbing, gas lines and any other work necessary for functioning. Consignee will provide required electrical supply, water connection, drain lines and gas lines at a point specified by the bidder inside the room. Bidder shall be responsible for the internal electrical cabling and gas lines inside the workbenches .Plumbing and drain line connection are also under the scope of the bidder.</p>
<p>Added para:</p>	<p><u>List of approved makes</u></p> <ol style="list-style-type: none">1. Plywood : Greenply / Century Ply /Western Ply2. Laminate : green lam /Merino/ Formica3. Hinges : Hettich/Hafele/ebco/Scanwolf-Malaysia/Grass/ Blum4. Drawer Slides : Hettich/Hafele/ebco/Scanwolf-Malaysia/Blum5. Hardware fittings : Tof – Italy/ Broen/ Watersaver /grohe6. Electrical socket : Legrand / Crab tree / Northwest/Schneider7. Wires : Polycab / Finolex / V-guard8.Laboratory chairs- Godrej/Wipro/Feather lite/Herman miller

All other terms and conditions remain unaltered.

.....End.....