

Setting Up of a Pharmacy at Ahmedabad Civil Hospital**SCHEDULE OF QUANTITIES**

| SL | ITEM | UNIT | QTY | Basic Rate (IN INR) | AMOUNT (IN INR) |
|----|--|------|-------|---------------------|-----------------|
| 1 | Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in charge. | Cum | 3.68 | | |
| 2 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth including Kota stone in outside Stair for Approach | Cum | 3.00 | | |
| 3 | Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge including Door Handle and all fittings. | Sqm | 14.00 | | |
| 4 | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, 12mm Thk Ply with Laminate in the bottom and 8mm Thk Float glass in Top all complete as per architectural drawings and the directions of Engineer-in-charge ONLY RELOCATION OF DOOR | SqM | 12.00 | | |

| | | | | | |
|----|---|-------|--------|--|--|
| 5 | Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters | SqM | 22.50 | | |
| 6 | Providing and fixing ball bearing for rolling shutters. | Each | 2.00 | | |
| 7 | Extra for providing mechanical device chain and crank operation for operating rolling shutters. | Each | 1.00 | | |
| 8 | Internal paint : 1 Coat primer, 2 coats water base paint distemper. ONLY ANTI BACTERIAL PAINT TO BE USED | SqM | 105.00 | | |
| 9 | Providing and fixing with 1.5sqmm and 2.5sqmm FRLS Copper wire,20/25mmPVC conduit,Concealed M.S.Switch box,ModulrPlates,Switches,fanRegulator,Sockets,Switches,For Lightspoints,fan.AC,fridge,Camera Power,Computer Power,Sign board,with material and Labour. | Point | 28.00 | | |
| 10 | Providing and fixing MDB with 1No 2Pole ELCB,4Nos Single pole MCB,Dressing,Termination and Commissioning. | Set | 1.00 | | |
| 11 | Lan/ Networking wiring only with data socket, plate, box, labour all complete as per drawing. | Mtr | 75.00 | | |
| 12 | providing and crimping socket for Lan wire connect to computer | Nos. | 8.00 | | |
| 13 | Providing and fixing pre wired Flourocent light fittings 600mm X 600mm as per detail with labour testing and commissing etc as required. | Nos. | 8.00 | | |
| 14 | providing and fixing ceiling fan 1200mm white in colour with clamp, labour all complete. | Nos. | 2.00 | | |

| | | | | | |
|----|--|------|-------|--|--|
| 15 | Supply, laying and testing of under noted sizes of Aluminium conductor XLPE insulated PVC sheathed & sleeved armoured and overall PVC sleeved 1.1 KV grade power distribution cables conforming to relevant IS code and as per specification in ground (in existing trenches) through pipe or on wall / racks cable trays including dressing and clamping the cable with MS zinc passivated clamps etc. as required. | | | | |
| | 4 x 16 sq.mm | Mtr | 55.00 | | |
| 16 | Supplying & making of end terminations with brass compression gland and Al. lugs for following sizes of PVC insulated and PVC sheathed/ XLPE Al. conductor cable of 1.1 KV grade as required. | | | | |
| | 4 x 16 sq.mm | Set | 2.00 | | |
| 17 | Supply,installation,testing and commissioning of Digital camera, 0.5 lux with 3/ 4 mm fixed lens with IR Leds for Day and night vision or equivalent complete as required in mini dome shape fixed type, including all wiring from the control module in existing PVC conduits complete as required. Make: honeywell, bosch, Hikvision, samsung | Set | 5.00 | | |
| 18 | Supply,installation,testing and commissioning of 8 – channel colour HD Video Mgmt system with 8 cameras inputs Built in multiplexer, Digital Video recorder, Video motion Detection system, aalong with 15" monitor, TCPIP network feature for remote monitoring & 500GB HDD Make: honeywell, bosch, Hikvision, samsung or equilant. | Each | 1.00 | | |
| 19 | Supply, installation , testing & commissioning 2trn split aircondition , including indoor and outdoor units , copper piping, drain piping, insulation, control and power cables between outdoor and indoor units, complete as required by Engineer-in Charge. Make: Voltas, Bluestar, Daikin. With 3.0 Mtr Standard Copper Pipe and Drain | Set | 2.00 | | |

| | | | | | |
|----|--|--------|--------|--|--|
| 20 | <p>MEDIUM SIZE MEDICAL STORAGE RACKS TYPE A: Open Wooden display laminated cabinets in plywood at the free floor area with proper provision of racks and shelves. Maximum height of the cabinet is depending upon the available height at the location. 450mm deep prelaminated storage unit with 18mm commercial ply shelves laminated bothside with front edge polish/painted and shutters fixed with hinges to be provided.The height of 450mm deep storage shall be 750mm from the ground. Rest of the height - 450mm wide 10mm thk clear float glass shelves to be fixed between laminated vertical 18mm ply with back. shelves to be fix with proper bracket holders. as per layout drawing. TOTAL 17 NOS CABINATE OF SIZE 2.40 MTR X 0.80 MTR CONSIDERED</p> <p>Note: Storage unite to include: Shutters of 18mm thick prelamine,10mm thick, back ply, hinges, individual locks, 150mm lonk 10mm dia 'H" handle, edge polish/painted match with outer laminate colour. Make laminate :Greenlam - 283 Sky blue / Merino / Century.</p> | Sq. ft | 351.21 | | |
|----|--|--------|--------|--|--|

| | | | | | |
|----|---|--------|--------|--|--|
| 21 | <p>MEDIUM SIZE MEDICAL STORAGE RACKS TYPE B: Open Wooden display laminated cabinets in plywood at the free floor area with proper provision of racks and shelves. Maximum height of the cabinet is depending upon the available height at the location. 450 mm deep prelaminated storage unit with 18mm commercial ply shelves laminated bothside with front edge polish/painted and shutters fixed with hinges to be provided.The height of 450mm deep storage shall be 750mm from the ground . Rest of the height - 400mm wide 10mm thk clear float glass shelves to be fixed between laminated vertical 12 mm ply with 10mm back Ply. shelves to be fix with proper bracket holders. TOTAL 12 NOS CABINET OF SIZE 2.10 MTR X 0.80 MTR CONSIDERED Note: Storage unite to include: Shutters of 18mm thick prelaminated,10mm thick back ply, hinges, individual locks, 10mm dia 'H" handle, edge polish/painted match with outer laminate colour. Make laminate :Greenlam - 283 Sky blue / Merino / Century.</p> | Sft | 225.60 | | |
| 22 | <p>COUNTER FOR MEDICAL: single level Counter of 900 mm from ground and Counter top at 1050 mm level. 18mm thk granite/marble to be used for counter top on 18mm thick commercial ply. Under counter storage unit (below 900 mm) to be fixed with individual locks and handles as per app. 600mm wide laminated door and openable counter top to be part of the counter as per design. The counter ends at both sides shall be in such a way that, it effectively separates the customers from the storage area. Cash drawer of suitable design is to be installed. Make PLYWOOD: Commercial. LAMINATE:GREENLAM, MARINO OR EQUIVALANT.</p> | Sq. ft | 118.36 | | |
| 23 | <p>Working Table,3'0"X 2'0" with 18mm Ply top and two Vertical support in store room as per DRW,with colour laminated sheet finish.</p> | Nos | 1.00 | | |
| 24 | <p>Revolving height adjustable chair with arm rest.</p> | Nos. | 10.00 | | |

| | | | | | |
|--|---|-------|-------|--|--|
| 25 | SIGN BOARD: Box Type Sign board with back Light and coloured transperant flex on front as per given design and letter.fittings will be with out stand. | Sft | 31.75 | | |
| 26 | Supplying and fixing of carbon dioxide fire extinguisher type 2 kgs. Capacity of approved make with wall mounting bracket as required conforming to IS: 2878/1976 (Push type). | Nos | 2.00 | | |
| 27 | Frosting of Glass with Film | Sqm | 15.00 | | |
| 28 | Supply of visitor chairs | Nos | 16.00 | | |
| 29 | Earthing with GI earth plate 600 x 600 x 6mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement with watering pipe complete with coke and salt etc. as required. | Each | 2.00 | | |
| 30 | supplying, laying testing commissioning of 1x4 sq.mm. CU flexible cable for earthing on surface or in recess in existing conduit complete as required. | Metre | 20.00 | | |
| 31 | Supply installation testing and commissioning of fully closed 6U rack cabinet with dual source power supply, all accessories as per specifications complete as required. | Nos. | 1.00 | | |
| Total amount for works | | | | | |
| Taxes & Statutory payments (Pl. specify) | | | | | |
| GRAND TOTAL (Final Bid Amount) | | | | | |