

HLL LIFECARE LTD

ANNEXURE

	Description	UOM	Quant- -ity	Rate	Amount
	<p>Construction of toilet blocks as part of CSR programme of HLL Lifecare Ltd, at Kanagala and villages surrounding Kanagala in radius of 10 Kms. Probable Villages-Kanagala, Haragapur, Konakeri, Solapur, Karajaga, Honnehalli, Baad, Akkiwat. Proposed number of toilets 38 Nos. type of toilet block will be decided based on site to site conditions and requirements.</p>				
1	<p>a) Excavation, supplying and fixing septic tank of 0.70 m diameter x 2.40 m long of cement concrete. b) Construction of square foundation of 1.60 m x 1.60m by wall of 0.23 m width 0.30 m below ground and 0.60 m above ground and filing excavated earth inside and compacting, concreting the surface with 1:2:4 cc of 0.10 m thick. c) Construction of 3 side walls half brick BBM wall/ cc blocks, front wall of 0.23m width leaving the space to fix the door. (Hight of wall- 2.5m) d) Supply and fixing cc sheet door (8mm thick) with cc frame with suitable holdfast, two nos of aldrops of suitable size. e) Providing and fixing WC pan integrated with foot rest of china clay (580mm x 440mm) with accessories such as trap, connecting pipe and air vent pipe. f) Supplying and laying of pre coated corrugated sheet/ corrugated cement sheet (1.5 mx 1.2m) for roofing, on two angles of 40x40x05mmx 1.20m L with concreting hold fast in the wall, using J hook bolt & nut and construction of half brick BBM on two side above the sheet. g) Providing and fixing 0.6 m x 0.3 m cc jail/ grill for ventilation at suitable hight. h) Providing 12mm plastering with cement mortar 1:6 (1 cement: 6 fine sand) i) Laying & dadoing glazed/ ceramic white tiles 0.30 m x0.30m to hight of 0.60m.</p>	Nos	01		

2	<p>a) Excavation, supplying and fixing soak pit with tank made of pre-fabricated CC rings (4 Nos) of 1.2 m x 1.2m instead of septic tank.</p> <p>b) Construction of square foundation of 1.60 m x 1.60m by wall of 0.23 m width 0.30 m below ground and 0.60 m above ground and filing excavated earth inside and compacting, concreting the surface with 1:2:4 cc of 0.10 m thick.</p> <p>c) Construction of 3 side walls half brick BBM wall/ cc blocks, front wall of 0.23m width leaving the space to fix the door. (Hight of wall- 2.5m)</p> <p>d) Supply and fixing cc sheet door (8mm thick) with cc frame with suitable holdfast, two nos of aldrops of suitable size.</p> <p>e) Providing and fixing WC pan integrated with foot rest of china clay (580mm x 440mm) with accessories such as trap, connecting pipe and air vent pipe.</p> <p>f) Supplying and laying of pre coated corrugated sheet/ corrugated cement sheet (1.5 mx 1.2m) for roofing, on two angles of 40x40x05mmx 1.20m L with concreting hold fast in the wall, using J hook bolt & nut and construction of half brick BBM on two side above the sheet.</p> <p>g) Providing and fixing 0.6 m x 0.3 m cc jail/ grill for ventilation at suitable hight.</p> <p>h) Providing 12mm plastering with cement mortar 1:6 (1 cement: 6 fine sand)</p> <p>i) Laying & dad doing glazed/ ceramic white tiles 0.30 m x0.30m to hight of 0.60m.</p>	Nos	01		
Total					
GST if applicable					
Grand total					

Note- Above quantity mentioned for collection of rate per unit of different configuration.

Proposed Number of toilets to be constructed- 38 Nos, may be single type or both types as mentioned above depending on requirement of location.

Signature of contractor with seal