

**HLL LIFECARE LIMITED, KANAGALA
ANNEXURE**

WORK : ANNUAL CIVIL REPAIR WORKS 2013-14

Sl. No.	Description	Unit	Qty	Rate	Amt
1	Earth work excavation for Foundation & removing the excavated earth outside as directed by Engineer-in-charge. Soft soil & Hard murum	Cum	250		
2	Earth work excavation for leveling & lowering the ground and removing the excavated earth to a distance as directed by engineer in charge including spreading, leveling, watering compacting in layers of 15 cms thick to the required slope using excavated earth (filling qty not to be measured & paid).	Cum	50		
3	Filling in plinth with murum from excavated stuff or selected earth brought from outside by spreading, watering and well consolidating in layers not exceeding 150mm thickness at a time etc. complete as directed.				
	a) Filling by excavated earth (only labour charges)	Cum	50		
	(b) Filling by out side earth (material & labour charges)	Cum	50		
4	Providing & laying Granite or Basalt or trap jelly concrete using 40 mm & down size jelly for foundation laid in 15 cms thick layers & well compacted including curing etc complete. Cement concrete 1:4:8.	Cum	30		
5	Providing & laying cement concrete using 20mm & down size Granite or trap laid 15 cms thick layers & well compacted, vibrating, curing finishing, form work, centering etc., complete.				
	(a) For foundation	Cum	30		
	(b) RCC lintel C. C 1:2:4 for lintel, (Exclusive of cost of steel & fabrication charges)	Cum	4		
6	Providing and constructing Coursed stone Masonry in 1:6 cement mortar in foundation & plinth with bond stones (2 m apart) and rough quoin stones including curing, pointing etc. complete as directed.	Cum	20		
7	Providing & constructing brick masonry with approved quality of modular brick of standard size with necessary scaffolding, curing for basement & super structure in C.M 1:6	Cum	30		
8	Providing (12mm) plastering to internal surfaces including curing, scaffolding, rounding of all corners wherever required smooth rendering in CM 1:4 with 12 mm thick plaster.	Sqm	400		
9	Providing (18mm) plastering to external surfaces including curing scaffolding rounding of all corners wherever required smooth rendering in CM 1:4 with 18 mm thick plaster complete	Sqm	350		

10	Providing & fabricating mild steel/HYSD steel reinforcement including straightening cutting, bending, hooking, lapping or welding wherever required, placing in position tying with binding wire of approved quality & gauge including the cost of binding wire & anchoring to the adjoining members wherever necessary including all laps etc., complete as per design, specification & directions.	Kg	500		
11	Providing & laying granite or basalt or trap jelly cement concrete (1:3:6) using 20 mm & down size jelly including mixing, laying, tamping, curing & smooth finishing for exposed faces & with necessary centering & form work etc., complete. Sills & coping & any other such works.	Cum	20		
12	Providing & laying granite or basalt or trap jelly cement concrete (1:3:6) using 20mm with 12 to 15 cms thick and down size granite jelly for flooring with topping of cement mortar 1:3, 12 mm thick with smooth finish, laid to proper slope & cut to the required pattern including mixing, laying, tamping, curing & smooth finishing etc complete.	Sqm	15		
13	Dismantling of existing BBM wall & disposing the debris outside as directed by Engineer-in-charge.	Cum	15		
14	Providing & laying first class antiskid Ceramic tiles of approved colour & size on existing tiled flooring including dismantling of existing flooring & shifting of debris, laying in cement mortar (1:3) of 50mm (min) thick, fixing of tiles by using cement slurry @ 4.4 Kg/Sqm and pointing the joints with white cement or plaster of paris cleaning, curing etc. (Make Johnson) (300 x 300mm)	Sqm	35		
15	Providing & dadoing first class Glazed ceramic tiles of approved colour & size on existing wall by dismantling existing tiles & shifting of debris, replastering, Fixing tiles by using cement, pointing the joints with white cement or plaster of Paris. Including cleaning, curing, conveyance of all materials, labours charges, lead & lift etc., complete. (Make: Johnson. 200x300)	Sqm	35		
16	Providing two coats of water proof cement painting of approved make, quality, colour & shade over one coat of primer including curing, necessary scaffolding & cleaning of paint stains wherever necessary etc., complete.	Sqm	200		
17	Providing two coats of water proof cement painting of approved make, quality, colour & shade curing, necessary scaffolding & cleaning of paint stains wherever necessary etc., complete.	Sqm	200		
18	Providing & applying two coats of oil bond distemper over painted surface of approved color & make including cleaning, plastering the surface corners wherever necessary etc complete.	Sqm	200		

19	Providing & applying of two coats of sandtex matt (navy blue) colour painting of approved make, quality & shade over one coat of primer including Rubbing entire surface, cleaning of surface polishing by sand paper, scaffolding, curing etc., complete.	Sqm	50		
20	Cleaning of rain water gutter of factory building once in three months of condom plan & Sanitary napkin plant as directed by Engineer-in-charge. (Height of the roof-9 mtrs)	No	4		
21	Providing & fixing door 6 paneled door of 32mm thick, including providing & fixing necessary standard quality brass fittings per door as follows, 2nos handles, hinges, tower bolts 1nos, latches 1NO, aldrop 1No, door stopper 1No, applying two coats of oil paint over a coat of primer etc. complete. Readymade door including 0.60mx0.60m cutting of door in the topside & fixing of plain glass of 4/5mm thick with wooden patti etc complete and both side view panels with plain glass and wooden frame including removing of old & fixing new as directed by Engineer-in-charge..Make-(Kalapturu)	Sqm	4		
22	Providing & fixing of flush tank including removing of old & fixing new as directed by Engineer-in-charge.(Make-Hindware/ parryware)	No	3		
23	Providing & fixing of Godrej door lock of 6 lever including removing of old & fixing new as directed by Engineer-in-charge.(Make-Godrej)	No	3		
24	Providing & laying to required line & slope roofing with corrugated asbestos cement sheets 6mm thick fixed with galvanized iron J or L hooks, bolts and nut 8mm dia C.I plain and bitumen washers over the existing purlins, rafters and trusses including removing old damaged sheets & fixing new, cost of material, labour etc complete as per specification.(Make: Swastik) height-12mtr	Sqm	20		
25	Providing & laying to required line & slope roofing with corrugated asbestos cement sheets 6mm thick fixed with galvanized iron J or L hooks, bolts and nut 8mm dia C.I plain and bitumen washers over the existing purlins, rafters and trusses including removing old damaged sheets & fixing new, cost of material, labour etc complete as per specification.(Make: Swastik) height-3-6mtr	Sqm	20		
26	Providing & fixing AC flat sheets wherever required after removing existing damaged sheets using bolts or self tapping screws. These are to be fixed for North light roof vertical structure. Height-10-12mtr	Sqm	25		
27	Providing & fixing AC flat sheets wherever required after removing existing damaged sheets using bolts or self tapping screws. These are to be fixed for North light roof vertical structure. Height-3-6mtr	Sqm	25		
28	Making & closing of holes using Brick masonry & plastering. Painting etc complete as directed by Engineer-in-charge. (Approx-Size of hole 0.40mX 0.40m)	No	2		
	Total amount				

Contractor sign with seal