

**HLL LIFECARE LIMITED, KANAGALA
ANNEXURE**

Work :Epoxy flooring, coving repair works at unipill plant

Sl. No	Description	Unit	Qty	Rate	Amount
1	Supply and applying of 1mm thick selflevelling epoxy flooring system to match the existing shde surface etc complete as directed by Engineer-in-charge.	Sqm	75		
2	Supply and applying of 3mm thick selflevelling epoxy flooring system for patch work to match the existing colour etc complete as directed by Engineer-in-charge.	Sqm	30		
3	Applying of Epoxy coving colour coating including filling of cracks etc complete as direted by Engineer-in-charge.	Rmt	100		
4	Making of new Epoxy coving floor to wall etc complete as directed by Engineer-in-charge .	Rmt	90		
5	Providing & applying of two coats epoxy paint as per the required shade etc complete as directed by Engineer-in-charge.	Sqm	500		
	Total amount				

Note-The work should be carried out as and when required.

Contractor sign with seal