

**HLL LIFECARE LIMITED, KANAGALA  
ANNEXURE**

<b>Name of the work: RCC Water Tank for Unipill Plant at KFB</b>					
<b>Sl. No</b>	<b>DESCRIPTION OF WORK</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	Cum	1.50		
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge	Cum	2.50		
3	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	25		
4	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc. Columns, Pillars, Piers, Abutments, Posts and Strutse	Sqm	210		
5	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars	Kg	3,750		
6	Brick work common burnt clay FPS (non modular) bricks of class designation 7.5 in superstructure above plinth level upto floor V level in all shapes and sizes in Cement Mortar 1:4 (1 cement : 4 coarse sand)	Cum	10		
7	20 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	Sqm	100		
8	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement 12 mm cement plaster	Sqm	90		
9	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade : New work (Two or more coats applied @ 1.43 ltr/ 10sqm over and including priming coat of exterior primerapplied @ 2.20 kg/ 10 sqm)	Sqm	120		
10	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.	Sqm	75		
	<b>Total amount</b>				

**Contractor sign with seal**