

HLL LIFECARE LTD

ANNEXURE

	Description	UOM	Quantity	Rate	Amount
1	Earth work excavation by manual means for drains, foundation and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift up to 1.5 m including cost of labour, tools & other to complete the work.	Cum			
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/ trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted, including all lead & lifts, cost of all materials of quality, labour, required to complete the work as per technical specifications. Mix 1:4:8 (M5) Using 40 mm nominal size graded crushed coarse aggregates.	Cum			
3	Providing and laying Cement concrete for floor/ pillar to hold pipes etc with 1:2:4 using 1cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size, including finishing complete as per Engineer in charge.	Cum			
4	Providing Random rubble masonry with hard stone in foundation and plinth concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement: 6 coarse sand)	Cum			
5	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement: 6 coarse sand)	Cum			

6	Providing Brick work with common burnt clay Non Modular bricks of class designation 3.5 in foundation and plinth in Cement mortar 1:6 (1 cement: 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer in charge of work,	Cum			
7	Providing 12 mm cement plaster with cement mortar 1:6 (1 cement:6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm			
8	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix: 1:6 (1 cement: 6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm			
9	Providing and fixing pre color coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per m2 as per IS: 277, in 240 mpa steel grade, 5-7 microns' epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in required length or as desired by Engineer-in-charge. The sheet shall be fixed using self-drilling/self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.(Jindal/ Tata make)	Sqm			

10	Providing and applying oil bound washable distemper of approved brand and manufacture to give an even shade New work (two coats) over and including water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm			
11	Providing and applying to finish walls with Acrylic Smooth exterior paint of required shade : New work (Two coat applied @ 1.67 ltr/10 m ² over and including priming coat of exterior primer applied @ 2.20 kg/10 m ²) with paint of approved quality to give an even shade, after thoroughly booming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge (ACE paint Asian or equivalent)	Sqm			
12	Providing/ fabricating and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. Complete. Hot finished B class welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge. Including applying of two coats of oil paint of approved make and shade. (2 / 1.5 inch` tube/ 30/40mm square tubes/ gusset plates/ bars etc)	Kg			
13	Providing and fixing both side pre polished Kadapa stone slab of uniform thickness for platform with rounding of fascia using mortar/ araldite to fix etc complete.,(30 to 45 mm thick)	Sqm			

14	Providing and laying red oxide flooring 40 mm thick, with an under layer of 30mm thick M-15 (1;2:4) cement concrete and top layer of 10mm thick plaster with 1:3 cement mortar mixed with red oxide finished with floating coat of neat cement mixed with red oxide (mix of same proportion), including cost of materials, labour, curing, complete as per specifications.	Sqm			
15	Providing and laying Cheered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand) Medium shade pigment using 50% white cement 50%.	Sqm			
	Total quoted basic				
	GST if applicable				
	Gross total				

Signature of contractor with seal