

**HLL LIFECARE LIMITED, KANAGALA
ANNEXURE**

Work : Reboring of Bore well (Drilling work)

Sl. No	Description	Unit	Qty	Rate	Amount
A	DIGGING OF BORE WELL				
1	Cleaning of bore well including yield testing of borewell for not more than 2 hours at the final depth with a minmum working of two hours continously with air compressor or suitable pump as per specification including the cost of transportation charges crew charges cost of consumables etc.	Each	1		
2	Redrilling of bore well				
a	0 to 50 meters	Rmt	50		
b	50 to 75 meter	Rmt	50		
3	Sinking of bore well of 150mm dia clear using fast rig in all strata including over burden upto 20mtr. Fixing of casing pipes,collars and cap with necessary cutting and threading including transportation of rig and supporting vehicles crew charges and cost of consumables etc., complete including yield testing at the final depth with minimum continuous working of compressor for one hour for piped water supply only Complete with all lead and lifts.				
a	50 to 100 meter	Rmt	50		
b	100 to 150 meter	Rmt	50		
4	Casing for bore well using 200mm PVC New pipe of 6kg/cm2 as directed by EIC.	Rmt	12		
5	Providing and fixing 150mm dia PVC/ MS cap	NO	1		
B	Pump & piping				
1	7.5HP Submersible pupm set.1)Stage-10, 2)H.P-7.5, Delivery-2 4) Make- Texmo 5)Required for bore well	NO	1		
2	GI pipe 'C' class size 2" with heavy duty color (Tata/zenith)	Rmt	125		
3	NRV size 2"-GM	NO	1		
	Total Amount				

Contractor sign with seal