

**Strengthening & Upgradation of Govt. Medical College, Kozhikode - Providing Parking Facilities**

	<b>PART A - CIVIL WORKS</b>				
<b>S.no</b>	<b>Description of work</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate Rs (in figures &amp; words)</b>	<b>Amount Rs</b>
	<b>Civil works</b>				
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	Cum	6.50		
2	Supply, Laying and consolidation of good earth with required watering and compacting with plate compactor, making good the undulations, including all Labour and machineries etc. complete as per the direction of the Engineer in Charge	Cum	140.4		
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	sqm	2810.0		
4	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	Cum	4.00		
	<b>Total - Part A - Civil works</b>				
	<b>Grand Total - Part A +Part B</b>				